

7535

30527

## REPORT of SURVEY for REPAIRS.

No. in Reg. Book. *5-* No. *5-* Survey held at *London* Date, first Survey *11<sup>th</sup> Nov<sup>r</sup>* Last Survey *16<sup>th</sup> Nov<sup>r</sup> 1869*  
 on the *Iron Screw "Plantagenet"* Master *G. Old*  
 in *Rup<sup>t</sup>* Tonnage *726* built at *London* When built *1869*  
 By whom built *Samuda* Owners *Samuda & Co*  
 Port belonging to *London* Destined Voyage *Mediterranean*  
 If Surveyed Afloat or in Dry Dock *Canal Dry Dock*  
 Last Survey, No. *7347* Port *Iron.* Classed *A1.*  
*14, 69.*

## REPAIRS, &amp;c.

Damaged by coming in contact with a pier. New plate on port side at upper turn of bilge amidships  $\frac{5}{8}$ " thick. A reverse angle iron 5 ft x 3" x 3" x  $\frac{7}{16}$ " riveted to strengthen a frame cracked on its inner edge. Double angle irons 4 ft x 3" x 3" x  $\frac{3}{8}$ " riveted to strengthen a tie stringer at top of bilge also cracked on the inner edge.

Bottom cleaned down and painted.

## Present Condition of the

Decks	<i>Good</i> <i>where</i> <i>seen.</i>	Greenails Rivets	<i>Good</i> <i>where</i> <i>seen.</i>	Windlass and Capstan	<i>Good and efficient.</i>
Waterways		Breasthooks and Stenson		Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c.	
Lower Deck Beams & Fastenings		Ditto Ditto at other places		Condition, how ascertained	
Planksheers		Keelsons		Sails	
Sheerstrakes		Clamps and Shells		Anchors No. of	
Topsides		Ceiling		Cables	
Wales		Rudder		Hawsers and Warps	
Plank (Bottom) and Counter		Copper		Standing & Running Rigging	
Engine Room Skylights	Caulking of				
Coal Bunker, Openings, Lids, &c.	Bottom, Deck, & Waterways				
General Observations and Opinion,					

The damage has been made good and she is fit in my opinion to remain as classed - A1.

J. H. Eastlake,

The Amount of Entry Fee.....£..... is received by me,

Special..... 1 : 1 : 0

Certificate (if required) : 5 :

Committee's Minute *26<sup>th</sup> November 1869*

Character assigned *A1*



© 2019

Lloyd's Register Foundation

IRON445 - 0145