

REPORT of SURVEY for REPAIRS.

of Damage

Rev 6/12/69

No. in Reg. Book. **No. 3950** Survey held at **Glasgow** Date **10th 22nd Nov** 18**69**
 on the **Em. Br. & Kiersale's** Master **McNellar**
 Tonnage **427** built at **Renfrew** When built **1863**
 By whom built **Readman** Owners **Gr. Caird & Co**
 Port belonging to **Glasgow** Destined Voyage **Glen Coaster**
 If Surveyed Afloat or in Dry Dock **Banclay's Caird Shipway**

Last Survey, No. **6187** Port **Iron.** Classed **B 1**
 SS No. **60 - 4. 60**

REPAIRS

Seven plates from and including sheerstrake, down on the starboard bow - two plates in forecabin and part of five frames - renewed, one buttstrap lower down taken off and extended in order to make good the upper corners of adjoining plates - a double buttstrap fitted to one butt in the sheerstrake where the shifting had been shortened, one plate in upper deck stringerplate doubled between the beams - where partly cut through a bracket plate added to broken knee end of upper deck beam. The bottom cleaned and recoated.

Present Condition of the

Decks	Good	Rails	Good	Windlass and Capstan	Good
Waterways	✓	Treenails	Good	Pumps	✓
Comings	✓	Breasthooks and Stemson	Good	Boats	Good
Upper Deck Beams & Fastenings	✓	Transoms, Pointers, and Crutches	Good	Masts, Yards, &c.	✓
Lower Deck Beams & Fastenings	✓	Timbers of the Frame at the openings	Good	Condition, how ascertained	✓
Planksheers	✓	Ditto Ditto at other places	Good	Sails	✓
Sheerstrakes	✓	Keelsons	Good	Anchors No. of	✓
Topsides	✓	Clamps and Shelves	Good	Cables	✓
Wales	✓	Ceiling	Good	Hawsers and Warps	Good
Plank (Bottom) and Counter	✓	Rudder	Good	Standing & Running Rigging	✓
		Copper	Good		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. **Good where seen**

This vessel is now in good and efficient condition eligible to remain as classed **B 1**

The Amount of Fee.....£ / : : is received by me,

Special..... 4 : 4 : :

Certificate (if required) : : : :

Committee's Minute **4th December 1869**

Character assigned **B 1**

record damage repair



© 2019 Lloyd's Register Foundation