

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. 66 No. 66 Survey held at London Date, first Survey 23rd Nov^r Last Survey 22nd Dec^r 1869
 on the Iron Ship "Warwick" Master J. Skinner
 Tonnage 1005 built at Pallion When built 1864
 By whom built Oswald Owners Temperley
 Port belonging to London Destined Voyage Calcutta
 If Surveyed Afloat or in Dry Dock James Iron Works Dry Dock

Last Survey, No. 6742 Port Iron Classed A1.

REPAIRS, &c.

(S. S. No 1-67.)
11, 68.
 Stress of weather damages. Front of poop, three poop rail stanchions, and one piece of rail, renewed on port side. Ten bulwark stanchions made good where broken (on port side) and the whole of them refastened. Three planks in deck renewed with Dantrie Fir. Strained rivets in butts of fore and main-mast renewed and a second stiffening angle iron added in way of each butt.

Outside cleaned down and painted, bottom coated with Mc. Innes's Composition.

Present Condition of the

Decks	} <u>Good</u>	Treenails	} <u>Good</u>	Windlass and Capstan	} <u>Good and efficient.</u>	
Waterways		Breasthooks and Stemson		Pumps		
Comings		Transoms, Pointers, and Crutches		Boats		
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c.	} <u>By examination when down.</u>	
Lower Deck Beams & Fastenings		Ditto Ditto at other places		Condition, how ascertained		
Planksheers		Keelsons		Sails		
Sheerstrakes		} <u>where seen.</u>		Clamps and Shelves	} <u>Good and</u>	
Topsides	Ceiling		Anchors No. of			
Wales	Rudder		Cables			
Plank (Bottom) and Counter	} <u>seen.</u>	Copper	} <u>When put on</u>	Hawsers and Warps	} <u>Sufficient.</u>	
Engine Room Skylights		Caulking of		Standing & Running Rigging		
Coal Bunker, Openings, Lids, &c.	Bottom, Deck, & Waterways	<u>Good where examined</u>	Cargo and Main Hatchways	<u>Good</u>	Hatches	<u>Good.</u>

General Observations and Opinion, The damages have been made good and the vessel put in efficient condition, fit in my opinion to remain as classed - A1.

J. H. Eastlake.

The Amount of Entry Fee.....£ 3 : — : — is received by me.

Special..... 1 : 1 : 0
 Damage Fee..... 2 : 2 : 0
 Certificate (if required) : : :

Committee's Minute 31st December 1869

Character assigned A1

record damage repairs



Lloyd's Register Foundation