

REPORT of SURVEY for REPAIRS.

Damage

Rev 14/3/10

No. in Reg. Book. **No. 3969** Survey held at **Kull** Date, first Survey **13th Aug** Last Survey **9th March 1870**
 on the **Iron Steamer James Cairns** Master **R. Vether**
 Tonnage **296** built at **Stockton** When built **1860**
 By whom built **226 Richardson** Owners **Rawson & Co**
 Port belonging to **Kull** Destined Voyage **Rouen**
 If Surveyed Afloat or in Dry Dock **In Gaidam's & in Ed Gibson's Dry docks & afloat in Prince's St**

Last Survey, No. **7602** Port **Iron** Classed **A 1**
 REPAIRS, &c. **S.S. No 3-69** **12-69**

How done - Ceiling in main hold and cement partly removed - Renewed
 five floor plates in two lengths with both straps double rivetted. One
 floor cut out & welded - two floors straightened - four leeward frames
 on top of floors repaired with doubling pieces. Main keelsons in
 way of damage cut adrift set fair & rivetted. Cement
 when removed renewed as also ceiling with 3/4 pine deck partly
 caulked - vessel outside cleaned & coated with paint

Present Condition of the

Decks	<i>Good when seen</i>	Ironails Ribs	<i>Good when seen</i>	Windlass and Capstan	<i>Good and sufficient</i>
Waterways		Breasthooks and Stemson		Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c.	
Lower Deck Beams & Fastenings		Ditto Ditto at other places		Condition, how ascertained	
Planksheers		Keelsons		Sails	
Sheerstrakes		Clamps and Shelves		Anchors No. of	
Topsides		Ceiling		Cables	
Wales		Rudder		Hawsers and Warps	
Plank (Bottom) and Counter		Copper When put on		Standing & Running Rigging	
Engine Room Skylights	<i>Good</i>	Caulking of	<i>Good</i>		
Coal Bunker, Openings, Lids, &c.	<i>Good</i>	Bottom, Deck, & Waterways	<i>Good</i>	Cargo and Main Hatchways	<i>Good</i>
General Observations and Opinion,		Scuppers	<i>Good</i>	Hatches	<i>Good</i>

Is now in good condition and eligible in my opinion to remain as classed A 1

The Amount of Entry Fee.....£ - : 10 : - is received by me, *M. Davidson*
 Special..... 1 : 1 : -
 Certificate (if required) : : -

Committee's Minute **15th March 1870**

Character assigned **A 1**
record damage repairs
Damage £24/-