

Report of Survey for Repairs of Engines and Boilers.

7959 Jan 270

No. 7959

No. in Reg. Book.

Survey held at Port Glasgow

Date, first Survey

March 4th

Last Survey

April 6th 1881

316 on the Machinery of the

J. S. Yacht Dobhran

(Number of Visits

5)

Tonnage, Gross

319

Built at

Port Glasgow

When built

Year

1846

Ditto, Net

180

Owners

J. V. Smith

Port belonging to

London

Diameter of Cylinder

26 3/4

Engines made by

Cumlish & Dunlop

When made

1846

Length of Stroke

24

Boilers made by

Cumlish & Dunlop

When made

1846

Pressure of Steam

65 lbs

If Surveyed Afloat or in Dry Dock

Afloat

Years assigned.

Character in Register Book.

Registered Horse Power

100

Classed

100 A1.

Last Survey No.

Port

"LLOYD'S M.C." "8.76"

Particulars of Repairs and Examination

On account of S. S. No. 1.

Cylinders and slide jackets opened out, pistons and slides examined, pumps examined, crank shaft and shafting generally examined, Propeller and sea connections examined, and the engines generally overhauled.

Safety valves examined, springs retested, and valves set. Main boilers retubed, and a few leaky places in shells recaulked, boilers afterwards tested to 120 lbs per sq. inch by water.

It was observed that a small cock is fitted to ship's bilge in way of lazarette with hose attached, for the purpose of occasionally freshening bilges, but as a lock-up gland is provided, and the spanner always in charge of the Master, it is submitted that this should not militate against the vessel's efficiency.

General Observations, Opinion, and Recommendation:

The engines and boilers being now in good and efficient condition, I am of opinion that the vessel is eligible to remain as classed "LLOYD'S M.C.", and to be noted "4.81".

Entry or Registering Fee ... £ 1: 0: 0

Survey Fee ... £ 2: 2: 0

Certificate (if required) ... £ 0: 2: 0

(Travelling Expenses, if any, £ - 10/6 £ 3: 4: 6

received by me,

April 1881

Committee's Minute

Friday, April, 8th. 1881.

Assigned

Alfred H. Alcock

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Greenock

Lloyd's Register Foundation

IRON 446-0201

It is submitted that this
document is eligible to have
the notification
Lloyd's No. 4.87
recorded

M
8/4/87



© 2019

Lloyd's Register
Foundation