

1976

REPORT of SURVEY for REPAIRS.

Rec 26/5/70

No. in Reg. Book.

No. 3987 Survey held at Hull on the *Howe's "Albert"*

Date, first Survey 15th April Last Survey 21st May 1870

Master *Henry*

264

Tonnage 384 built at Hull

When built 1856

By whom built *C & W Earle*

Owners *Wm Lawson &*

Port belonging to Hull

Destined Voyage Rotterdam

If Surveyed Afloat or in Dry Dock *On Earle's slipway & afloat in Princes St*

Last Survey, No. 4331 Port Iron.

Classed 9 expired (C.S. 64) 3.54

REPAIRS, &c. in accordance with the Rules Survey No 3 - Ceiling lifted where required Cement Hammer & found good. Cement removed at parts & the plating drilled thickness 8.6 bottom, 11.6 sides - Cement extended out in bilges at Man hold - Ceiling relaid - Plating outside and inside above Ceiling & Cement coated with paint. Tar & black lead. Boilers & Engines overhauled - Several shifts of deck in way of Engine & Boiler space lined with yellow pine deck partly sheathed - Steek Caulked Chain Cables on Deck

Present Condition of the

Decks	<i>Good</i>	Freemasts <i>hitch</i>	<i>Good</i>	Windlass and Capstan	<i>Good</i>
Waterways		Breasthooks and Stemson		Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c.	
Lower Deck Beams & Fastenings		Ditto Ditto at other places		Condition, how ascertained	
Planksheers		Keelsons		Sails	
Heerstrakes		Clamps and Shelves		Anchors No. of	
Topsides		Ceiling		Cables	
Wales		Rudder		Hawsers and Warps	
Plank (Bottom) and Counter		Caulking of		Standing & Running Rigging	
Engine Room Skylights <i>Good</i>		Bottom, Deck, & Waterways <i>Good</i>			
Coal Bunker, Openings, Lids, &c. <i>Good</i>		Scuppers <i>Good</i>		Cargo and Main Hatchways <i>Good</i>	Hatches <i>Good</i>

General Observations and Opinion, *Is now in good condition and eligible in our opinion to be classed B 1 & marked (S.S. No 3-70) & marked Cemented 1864*

The Amount of Entry Fee.....£ 4: - : - is received by me. *M Davidson*

Special..... 4: 4: -

Certificate (if required) : 5: -

Committee's Minute 27th May. 1870

Character assigned *B 1* *Wm Gemmell £1.11-*

180446-0218