

REPORT of SURVEY for REPAIRS.

of damage

Rec 13/2/91

No. in Reg. Book: **No. 3279** Survey held at Glasgow Date 1st Dec 1871 to 10th Feb 1871
 on the Iron Bk "Cingalese" Master Scott
 Tonnage 690 built at Glasgow When built 1869
 By whom built John & Glas. & B Co Ltd Owners Wenmouth &
 Port belonging to Glasgow Destined Voyage Glas Trinidad
 If Surveyed Afloat or in Dry Dock Wm Stephens Shipway

Last Survey, No. 7588 Port Iron Classed A

REPAIRS

12.69

This vessel had been temporarily repaired at Quebec.

Now done

The length of keel removed and half of its length renewed by welding, and, on the Starboard side, nine floor plates, two shifts of double-frame angle-irons, five entire frames, four others shifted, and eighteen reverse frames, renewed. The bilge-keelson angle-irons, in the range of the foregoing, renewed. The hold beam-stringer plates and several beam ends riveted, and thirteen plates between keel and top of bilges renewed. keelsons one refitted. On the port side, one frame and reverse frame shifted. Four plates renewed and one refitted; all close ceiling from the after bulkhead lifted and, with the cement, renewed. Four planks of deck replaced. The vessel recoated outside and in, and the damaged hawsers replaced.

Decks	Good	Treenails Ribs	Good	Windlass and Capstan	Good
Waterways	5	Breasthooks and Stemson	7	Pumps	5
Comings	5	Transoms, Pointers, and Crutches	7	Boats	Just
Upper Deck Beams & Fastenings	5	Timbers of the Frame at the openings	5	Masts, Yards, &c.	7
Lower Deck Beams & Fastenings	5	Ditto Ditto at other places	5	Condition, how ascertained	Truff
Planksheers	7	Keelsons	5	Sails	7
Sheerstrakes	5	Clamps and Shells	5	Anchors No. of	Three
Topsides	7	Ceiling	5	Cables	2
Wales	7	Rudder	5	Hawsers and Warps	Seven
Plank (Bottom) and Counter	7	Copper <i>16 1/2 p/7</i> When put on		Standing & Running Rigging	7

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where examined

This vessel is now in good and efficient condition eligible to remain as classed

The Amount of Fee.....£ 2 : " : " is received by me,

Feb 11 Special..... 6 : 6 : "

Certificate (if required) - : " : "

Committee's Minute 14th February 1871

Character assigned A

record damage repair



© 2019

Lloyd's Register Foundation

IRON448-0046