

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No 23079** Survey held at **Birkenhead** Date, first Survey **11 Aug** Last Survey **5 Sept** 18**90**
 Tonnage **1002** built at **Newcastle** When built **1865-3mo**
 By whom built **Thos J. S. B. Co** Owners **Girvin &**
 Port belonging to **Liverpool** Destined Voyage
 If Surveyed Afloat or in Dry Dock **Shes G R Clover Ho's dry dock**

Last Survey, No. **8213** Port, **Iron** Classed **A 1**
 (S. S. L. 703-70) 570

REPAIRS, &c.

Through damage sustained
 Lower piece of stem scarping to keel 17 1/2 ft long new. also 2 Garboard plates Each side & 2 plates Starboard side above Garboards in way of new stem. one plate forward and one plate aft in flat of bottom Port side. 5 plates on Port bilge & 3 side plates. one floor & 2 frames scarping. 2 plates taken off rollers and refitted. one edge of garboard plate straightened. a good many rivets in garboard (lower edge) new. 3 planks of the partial awning deck new. & the deck recaulked. Coal bunker bulkhead straightened and additionally stayed. Engine cleaned. Monkey boiler repaired. painted inside and outside

Present Condition of the

Decks	Good	Greenails	Rivets part new	Windlass and Capstan	Good
Waterways		Breasthooks and Stemson		Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c.	
Lower Deck Beams & Fastenings	and	Ditto Ditto at other places		Condition, how ascertained	and
Planksheers		Keelsons		Sails	
Sheerstrakes		Clamps and Shelves		Anchors No. of	
Topsides		Ceiling		Cables	
Wales		Rudder		Hawsers and Warps	Suffr
Plank (Bottom) and Counter		Copper	Cement When put on 1870	Standing & Running Rigging	
Engine Room Skylights		Caulking of		Cargo and Main Hatchways	
Coal Bunker, Openings, Lids, &c.		Bottom, Deck, & Waterways	Good	Hatches	

General Observations and Opinion, **She is now in efficient condition and in my opinion may continue as Classed**

The Amount of Entry Fee.....£1 : : : is received by me,

Special.....2 : 2 : - 10/12/91

Certificate (if required) " : " : "

Committee's Minute **Liverpool 19th December 1891**

Character assigned **A 1** Record damage repairs

cost on damage £6. 6. of 10/12/91

Wm. E. Davey
 Surveyor

REPORT OF SURVEY FOR REPAIRS

"
Ogden & Co.
" 23049



© 2019
Lloyd's Register
Foundation