

Iron 10185

32354

## REPORT of SURVEY for REPAIRS.

No. in Reg. Book. *290* No. *1* Survey held at *London* Date, first Survey *March 12* Last Survey *April 29* 18 *72*  
 on the *S.S. "John Brogden" (Iron)* Master *G. Chetham*  
 Tonnage *719.28* built at *Newcastle* When built *1866*  
 By whom built \_\_\_\_\_ Owners *A Brogden*  
 Port belonging to *Swansea* Destined Voyage *Swansea*  
 If Surveyed Afloat or in Dry Dock *Cubitt Town Slipway & Puddicombe's Yard*  
 Last Survey, No. *7104* Port *Iron* Classed *B* *5.69*

## REPAIRS, &amp;c.

Now done, lengthened 40 feet - as per Committee's letter, topside strake doubled for  $\frac{3}{4}$  the length, upper deck stringer increased to 36 inches for  $\frac{1}{2}$  the length - lower deck stringer attached to the outside plating from the engine room bulkhead to the bow tank, water ballast tank lengthened the same as the ship and a double angle iron stringer  $3 \times 3 \times \frac{1}{2}$  fitted in the tween decks. The whole of the ceiling lifted and the bottom re-centred, plating cleaned outside and repainted -

Length 199.5  
 Breadth 27.4  
 Depth 15.6

## Present Condition of the

## Decks

## Waterways

## Comings

## Upper Deck Beams &amp; Fastenings

## Lower Deck Beams &amp; Fastenings

## Planksheers

## Sheerstrakes

## Topsides

## Wales

## Plank (Bottom) and Counter

## Engine Room Skylights

## Coal Bunker, Openings, Lids, &amp;c.

## Scuppers

## General Observations and Opinion,

## Breasthooks and Stems

## Transoms, Pointers, and Crutches

## Timbers of the Frame at the openings

## Ditto Ditto at other places

## Keelsons

## Clamps and Shelves

## Ceiling

## Rudder

## Copper

## When put on

## Caulking of

## Bottom, Deck, &amp; Waterways

## Windlass and Capstan

## Pumps

## Boats

## Masts, Yards, &amp;c.

## Condition, how ascertained

## Sails

## Anchors No. of

## Cables

## Hawsers and Warps

## Standing &amp; Running Rigging

The Amount of Entry Fee.....£ 2 : -

is received by me,

Special..... 6 : 6

Certificate (if required) : :

Committee's Minute

31<sup>st</sup> May 1872

Character assigned

B

recess lengthened

Mc ITUN

Thos W. Wain

Mem 20/1/80



© 2019

Lloyd's Register Foundation