

10975
32772

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** Survey held at London Date, first Survey 11 Last Survey 23 Dec^r 1872
 on the Iron Ship "Star of Denmark" Master J. Mayne
 Tonnage 998 built at Belfast When built 1863
 By whom built Harland & Co. Owners Corry & Co.
 Port belonging to Belfast Destined Voyage Batavia
 If Surveyed Afloat by in Dry Dock Nipanis Dry Dock. and E. J. Dock

Last Survey, No. 9855 Port Inon Classed * A 1

REPAIRS, &c.

Now done, on account of leakage at S.S. Nov. '69 / 272
Sea arising from deterioration of a plate in the
bottom, vessel placed on blocks in dry dock; on
examination, found the whole of the close ceiling
in the forehold, had been cleared away, which was
reported to have been done at Sea, in order to discover
the cause. The stoppage of which, reflects great credit
on the Captain, on account of the means used
to save the Ship. The whole of the cement, from
the middle line to bilge, on each side, in the fore
compartment, viz between first and second bulk
heads, has now been broken up, and removed, and
an examination made of the inner surface of plating

Present Condition of the

Decks	Freeboards	Pivots	Windlass and Capstan
Waterways	Breasthooks and Stemson		Pumps
Comings	Transoms, Pointers, and Crutches		Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Grad	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	where	Condition, how ascertained
Planksheers	Keelsons	seen	Sails
Sheerstrakes	Clamps and Shelves		Anchors No. of
Topsides	Ceiling		Cables
Wales	Rudder	Paint	Hawsers and Warps
Plating	Copper	When put on	Standing & Running Rigging
Plant (Bottom) and Counter	Caulking of		
Engine Room Skylights	Bottom, Deck, & Waterways		
Coal Bunker, Openings, Lids, &c.	Scuppers		Cargo and Main Hatchways
General Observations and Opinion,			Hatches

The vessel now appears to be in a good and efficient condition, eligible to remain "A 1" as classed.

Henry J. Gervell

The Amount of Entry Fee.....£ 2 : - : - is received by me,
 Special..... 3 : 3 : 0
 Certificate (if required) : 5 :

Committee's Minute 10th January 1873

Character assigned A 1

Record repair

J. G. M.



© 2019
Lloyd's Register
Foundation

IRON 453-0027

"Star of Denmark". Report Cont^d.

in this part of the Vessel. - The plate in bottom
 on Starboard Side - 3 Shakes up from Reel, in
 way of Foremast; and about 400 Rivets removed;
 the Cement made foul, and Ceiling replaced;
 outside plating cleaned, and the bottom coated
 with McInnes's Patent Paint - Aug. 7