

REPORT of SURVEY for REPAIRS.

11689

33208

No. in Reg. Book. **No.** Survey held at London Date, first Survey 2nd July Last Survey 16th July 18 73
 on the Terrace "Pyhope" Master J. Mullins
 Tonnage 698 built at Lunderland When built 1860-7 mo
 By whom built Living Owners H. Taylor
 Port belonging to London Destined Voyage Lunderland
 If Surveyed Afloat or in Dry Dock Afloat in the Victoria Docks
 Last Survey, No. 9291 Port Iron Classed FA/1

REPAIRS, &c.

Damage thro' collision 15.5.73-69, 9.72.
 On 'Starb. Quarter' One main frame with reversed, - frame attached set fair, one short length of raised quarter deck stringer-plate renewed, as also one length of gunwale angle iron in way of same; one length of covering-board of $3\frac{1}{2}$ in Oak. Two planks of deck next thereto of $2\frac{1}{2}$ in Pine, fastened with nut and seven bolts of iron $1\frac{1}{2}$ in diam; gunwale moulding, together with the fittings of deck and side repaired. One plate in upper strake of side plating renewed $\frac{5}{16}$ thick, and one plate in the strake next down (Sheer Strake), new $28 \times \frac{5}{16}$. Caulked in way of the new work.

Present Condition of the

Decks	Trunnels	Rivets	Windlass and Capstan
Waterways	Breasthooks and Stemson		Pumps
Comings	Transoms, Pointers, and Crutches		Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings		Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places		Condition, how ascertained
Planksheers	Keelsons		Sails
Sheerstrakes	Clamps and Shelves		Anchors No. of
Topsides	Ceiling		Cables
Wales	Rudder		Hawsers and Warps
Plank (Bottom) and Counter	Copper	When put on	Standing & Running Rigging
Engine Room Skylights	Caulking of		Cargo and Main Hatchways
Coal Bunker, Openings, Lids, &c.	Bottom, Deck, & Waterways		Hatches
General Observations and Opinion,			

Is now in good and efficient condition.
 and in my opinion eligible to remain as classed

J. H. Crozier

The Amount of Entry Fee.....£ 2 : - : is received by me,

Special.....1 - 1

Certificate (if required) : :

Committee's Minute 5th August 18 73.

Character assigned FA/1



© 2019

Lloyd's Register Foundation