

REPORT of SURVEY for REPAIRS.

12325

No. in Reg. Book. 84 No. 3408 Survey held at Bristol Date, first Survey 27 Jan^y Last Survey 31 Jan^y 1874
 on the S. S. Lady Lycett Master _____
 Tonnage 1833 built at Glasgow When built 1872 - June
 By whom built Dodd & Glas Co Owners Mercantile Steam Ship Co
 Port belonging to London Destined Voyage Bristol to Cardiff, thence India.
 If Surveyed Afloat or in Dry Dock Dry Dock
 Last Survey, No. 11226 Port from Classified 90 dt.
 REPAIRS, &c. 3.73

This vessel has been docked and had Bottom scraped and recoated

One of the plates right forward at the 17 feet mark on the side, having been damaged at N. York, has now been cut and part renewed. The rivetting however has not been completed, it is to be done at Cardiff, for which Port the vessel leaves today. The Butt strap to new plate is to be the width of the space between frames and overlap the flange of one frame which is slightly fractured there. An additional Breasthook has been recommended to be fitted between the present lower hook and Nelson, owing to slight movement there.

Present Condition of the

Decks	Keelsons	Windlass and Capstan	Good
Waterways	Breasthooks and Stemson	Pumps	do
Comings	Transoms, Pointers, and Crutches	Boats	do
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.	do
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained	from deck
Planksheers	Keelsons	Sails	well found
Sheerstrakes	Clamps and Shelves	Anchors No. of	313. 15 & 16 dgs
Topsides	Ceiling	Cables	complete
Wales	Rudder	Hawsers and Warps	suff ^y
Plank (Bottom) and Counter	Copper Bottom When put on	Standing & Running Rigging	good
Engine Room Skylights	Caulking of	Cargo and Main Hatchways	good
Coal Bunker, Openings, Lids, &c.	Bottom, Deck, & Waterways	Hatches	good
General Observations and Opinion,			

When the work described above, is completed, the vessel will be eligible to remain as classed.

The Amount of Entry Fee.....£ 3 :

Special.....

Certificate (if required) :

Committee's Minute

10th February 1874

Character assigned

90 A

N.B. The repairs is entered in the above report have been completed here

Letter to Mr. Lister, Cardiff 2/2/74
 10/2/74

(not been received by me.)
 Paid Vice Lister annexed

Thomas Congdon

2019

Henry F. Gyrrell

Cardiff 4/2/74