

REPORT of SURVEY for REPAIRS.

Rec 25/6/74

No. in Reg. Book. **No. 20** Survey held at Copenhagen Date, first Survey 14th June Last Survey 22nd June 18 74.on the "Anglo Dane" Ship Master MaresenTonnage 646 built at Newcastle on Tyne When built 1866-7 No.By whom built Leslie Owners The United Steamship CompanyPort belonging to Copenhagen Destined Voyage Baltic EnglandIf Surveyed Afloat or in Dry Dock in dry dock high mountedLast Survey, No. 10419 Port Iron Classed A-1

S.S. No. 69 7.72

REPAIRS, &c.

The "Anglo Dane" has undergone a large repair on Machinery and Boilers chiefly, but at same time also on Hull & Equipment in general. — She was put into dry Dock, had the whole of her ceiling boards removed. The old Cement repaired and renewed up from keel to bilges. I had several Rivets & Bolts drove and tested, and found same as well as plates all over in a good state. Bottom & Topsides scraped clean all over, and 3 coats of patent lead & paint put on. Decks & waterways have been caulked, Windlass unhooking. Chances ranges, Inventory thoroughly examined.

The "Anglo Dane" had also her awning deck lengthened 22 feet with angle iron 3½ by 3 and plates ¾ inch whole length of waterways and 3 inch Deck Planks, the necessary stringers and fastenings on Beams 3½ by 3 applied and done by good workmanship.

Present Condition of the

"Anglo Dane" is very efficient in all parts.

Decks partly new & goodWaterways goodComings Iron very high & goodUpper Deck Beams & Fastenings good

Lower Deck Beams & Fastenings

Planksheers

Sheerstrakes

Topsides goodWales good

Plank (Bottom) and Counter

Engine Room Skylights

Coal Bunker, Openings, Lids, &c.

Scuppers

Cargo and Main Hatchways

Hatches

General Observations and Opinion,

It is my firm opinion that the "Anglo Dane" is in a good & efficient condition now, fit to carry dry goods safe, and that she is deserving of continuation of her original class viz. A-1 further on from now.

The Amount of Entry Fee.....£ 2 : 0 : 0 is received by me, with six pounds nine

Survey Special..... 4 : 4 : 0

Certificate (if required) 0 : 5 : 0

Committee's Minute 26th June 18 74

Character assigned

A-1

S.S. No. 2-74

IRW