

34264

Rec'd 5-11-74

See below
as to date
of Entrance
Hope

	Years assigned.	Character in Register Book.
Classed	100 A1	6. 74

The Cargo of this vessel caught fire while on her voyage from London to Cape of Good Hope, and which necessitated her return to this Port.

The only damage to the Hull, consisted of the under side of middle deck being badly charred in two Beam spaces before the Fore Hatchway, the Lie plate of middle deck Beam drawn downwards about 2" in one space, and one Beam straightened about $\frac{3}{4}$ of an inch.

The deck alluded to, has been temporarily repaired
the voyage, by sheathing the upper surface of the charred
portion with 1/2" Deal. The top plate cut, set into place and double
bolted. Two additional pillars fitted to beams.

Present Condition of the		Tonnage		Windlass and Capstan	
Decks	Good	Ruins	Good		Good
Waterways	do	Breasthooks and Stemson	do	Pumps	do
Comings	do	Transoms, Pointers, and Crutches	do	Boats	do
Upper Deck Beams & Fastenings	do	Timbers of the Frame at the openings	do	Masts, Yards, &c.	do
Lower Deck Beams & Fastenings	do	Ditto Ditto at other places	do	Condition, how ascertained	from the CB
Planksheers	do	Keelsons	do	Sails	well found
Sheerstrakes	do	Clamps and Shelves	do	Anchors No. of	3/3 1/2 & Wedges
Topsides	do	Ceiling	do	Cables	complete
Wales	do	Rudder	do	Hawsers and Warps	sufficient
Plank (Bottom) and Counter	do	Copper	When put on	Standing & Running Rigging	good
Engine Room Skylights	Good	Caulking of		Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	Good	Bottom, Deck, & Waterways	Good	Hatches	Good
Scuppers	Good				
General Observations, Opinion as to Class, &c.					

This Vessel has been examined as far as practicable in the Fire Hold and the locality of the fire (the other Holds occupied with Cargo) and all found good and free from injury. I am of opinion she may remain as classed, subject to the Committee's approval of the Charred deck being removed on Vessel's return.

The Amount of Entry Fee £ " : " : } received by me, } Thomas Congdon
 Special £ ✓ : 1 : } 19/11/ 1874 }
 Certificate (if required) £ : 5 : }

Surveyor to Lloyd's Register of British and Foreign Shipping.

(Travelling Expenses, if any, £ _____)
Committee's Minute 20th November 1874

Character assigned German 100A

Supplement to Lloyd's Register of British and Foreign Shipping.

© 2019

Lloyd's Register
Foundation

IRON 460-0062