

(Iron)

13978

374475

# REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. 39 No. 1022 Survey held at London Date, first Survey Oct 22<sup>nd</sup> Last Survey Oct 26<sup>th</sup> 1874  
on the Ship "Rakaia" Master Mc Innis  
Tonnage 1022 built at Sunderland When built 1873 - 11 mo.  
By whom built Blumer Owners N. Zealand Shipg. Co.  
Port belonging to London Destined Voyage New Zealand.  
If Surveyed Afloat or in Dry Dock Canal Dry Dock  
Last Survey, No. 12164 Port Iron Classed 100 AL 12-73

REPAIRS, OR EXAMINATION AS PER RULE

Bottom sighted, cleaned & painted with  
Two coats of White Zinc & one of Tallow -  
Iron Bowspit found to be fractured at the outer  
end of diaphragm plate; the fractured plate & the  
fractured butt strap renewed, and a doubling plate  
introduced, giving a shift beyond diaphragm plate.

Present Condition of the

Decks	} Good	Trunnions	Rivets	} Good	Windlass and Capstan	Good
Waterways		Breasthooks and Stomoon	} Good		Pumps	2 B-2 M. do
Comings		Transoms, Pointers, and Crutches			Boats	5 (2 as life) do
Upper Deck Beams & Fastenings	} Firm	Timbers of the Frame at the openings		Masts, Yards, &c.	do	
Lower Deck Beams & Fastenings		Ditto Ditto at other places	Condition, how ascertained	Inquiry & Observation		
Planksheers		Keelsons	part seen	Sails	double suit Good	
Sheerstrakes	} Good	Clamps and Shelves	Ceiling	part seen	do	
Topsides		Rudder	Cables	part seen	do	
Wales		Copper	paint When put on	Hawsers and Warps	good & sufficient.	
Plank (Bottom) and Counter		Caulking of	Good	Standing & Running Rigging	Good	
Engine Room Skylights	✓	Bottom, Deck, & Waterways	Good	Cargo and Main Hatchways	Good	
Coal Bunker, Openings, Lids, &c.	✓	Scuppers	Good	Hatches	Good	

General Observations, Opinion as to Class, &c.

This vessel is in a good and efficient condition,  
fit for the safe conveyance of dry and perishable  
goods to and from all parts of the world, and  
eligible in my opinion to remain as Classed  
100 AL.

The Amount of Entry Fee ... £ ... received by me, ...

Special ... £ 2 : 2 : 0 { 25/2 / 1875 }

Certificate (if required) ... £ : 5 : 0

(Travelling Expenses, if any, £ ...)

Committee's Minute 26<sup>th</sup> February 1875

Character assigned

100 AL

TBW

J. Shilston

Surveyor to Lloyd's Register of British and Foreign Shipping.

© 2019

Lloyd's Register Foundation

IRON460-0239