

Dec 11/3/75

No. in  
Reg. Book.

No. in Reg. Book. **No. 11048** Survey held at Sunderland Date, first Survey February 16<sup>th</sup> Last Survey March 5<sup>th</sup> 1845  
on the Ship "Poonah" Master - Stacey

Tonnage 1199 built at Lumsailand When built 1864 (10 mo.)

By whom built	Pile	Owners
		G. D. Fisher.

Port belonging to London Destined Voyage Newcastle, New S. Wales

If Surveyed Afloat or in Dry Dock South Graving Dock

*Last Survey, No.* 11991. *Port* London from *Classed* 2

<i>Classed</i>	Years assigned.	Character in Register Book.
		<del>X</del> <i>A</i> <i>1</i>
<i>E.S. No 1-72</i>		<i>10.72</i>

REPAIRS, OR EXAMINATION AS PER RULE Annual Survey

Keel and Bottom examined found in good condition; Renewed the Port Cat-head for defects; Damage by indentations, &c, removed and refitted three Sheerstrake plates Starboard side, removed many rivets from the Plating, &c, Vix, Starboard Bow, Sheerstrakes &c port side near amidships, and Gunwale angle &c each side; introduced packing or liners on the frames, for fairing, and reriveted the same; Repaired two frames and two Beam ends St<sup>d</sup> side amidships; Renewed pintles to Rudder and repaired side lights or Ventilators about 13 Nos; Paved the Bottom with 2 Coats Lime & one Tallow, topsides painted.

about 500 tons Cargo in Hold

Present Condition of the

### *Present Condition of the*

Decks	Good	Fastenings	Rivets	Good	Windlass and Capstan	Good
Waterways	"	Breasthooks and Stemson	"	"	Pumps	2 Main "
Comings	"	Transoms, Pointers, and Crutches	"	good	Boats	6 No "
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	White	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Seen	Condition, how ascertained	insp <sup>n</sup> from SK
Planksheers	"	Keelsons	"	not Seen	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors	No. of 3 B. 1 S. 2 K good
Topsides	"	Ceiling	"	part Seen, good	Cables	"
Wales	"	Rudder	"	"	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	"	Paint When put on now	Standing & Running Rigging	good
Engine Room Skylights	"	Caulking of	"	"	Cargo and Main Hatchways	good
Coal Bunker, Openings, Lids, &c.	"	Bottom, Deck, & Waterways	"	good	Hatches	good
Scuppers	"	good	"	good		

General Observations, Opinion as to Class, &c.

She is now in good and efficient condition and fit in my opinion to remain as Classed. Viz. \*A.1.

The Amount of Entry Fee ... £ 5 : 5 : 0 received by me, }  
*Damage Survey* Special ... £ 1 : 1 : 0 *10<sup>th</sup> March 1875* }  
 Certificate (if required) ... £ " : 5 : "

Travelling Expenses, if any, £             
Committee's Minute 12<sup>th</sup> March 1872

Character assigned \_\_\_\_\_

Joseph Keen,  
Surveyor to Lloyd's Register of British and Foreign Shipping.

© 2019

Lloyd's Register  
Foundation

1RON460-0283