

Workmanship. Are the butts of plating planed or otherwise fitted? Yes 14146 Lin
Do the edges of the carvel work and of the butts lay close together throughout their length without requiring any making good of deficiencies? Yes
Are the fillings between the ribs and plates solid single pieces? Yes
Do the holes for riveting plate to frames, butt straps, or plate to plate, &c., conform well to each other? Yes
Are the rivet holes well and sufficiently countersunk in the plate and punched from the faying surfaces? Yes
Do any rivets break into or through the seams or butts of the plating? Yes a few at Butts at Stem & keel

Masts, Bowsprit, Yards, &c., are Iron in good condition, and sufficient in size and length. If of Iron or Steel give
Scantlings of Plating, Angle Irons, &c., and further explain by a Sketch showing how the lower Masts and Bowsprit are constructed, showing
the number of Plates and Angle Irons, mode of riveting, quality of Materials, and if stamped with Maker's name.

State also Length and Diameter of Lower Masts and Bowsprit Fore Mast 89' 9" Main Mast 86' 2" formed of two
plates doubling 8' 6" thick, double riveted at Butts and Stems, Ribs 3/4 spaced 3 1/2"
apart. plating doubled at Spar Deck for 7 feet in length and at
Main deck for 2 feet

NUMBER for EQUIPMENT		Fathoms.		Inches.		Test per Certificate.		Length. & Size req'd pr Rule.		Test req'd per Rule.		ANCHORS, N ^o .		Weight. Ex. Stock.		Test per Certificate.		Weight req'd per Rule.		Test req'd per Rule.	
36.491		300		2 1/8		81 tons sent		300 of 2 1/8		462.0 tons		Bowers ... 4		43.2.2.1		38.7.3.7		40.0.0		35 1/2 tons	
SAILS.		CABLES, &c.		Chain Lloyd's Patent		Hawser dates		11 1/2 May 1872 & signed				(State Machine where Tested, Date, and name of Superintendent.)		42.3.3.14		37.15.2.14		40.0.0		35 1/2 tons	
Fore Sails,		Fore Top Sails,		Fore Topmast Stay Sails		Main Sails,		Main Top Sails,				Stream ... 1		41.2.2.2		37.1.2.2		34.0.0		31 1/2 tons	
Hemp Strm Cbl		90		1 1/4		Hawser ... 90		10				Kedges ... 2		35.1.12		32.13.0.14		40.0.0		35 1/2 tons	
Towlines		90		12		Towlines		12				Including Stock		15.3.6		15.0.0					
Warp ... 180		8				Warp ... 180		8						9.0.8		4.2.0					
quality good		180		15 rollers										3.3.8		3.3.8					