

REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. **No.** 3440 Survey held at West Hartlepool Date, first Survey 25th March Last Survey 12/4/75 1875
on the Law S^r Mary Master H. Lawson

Tonnage 846 built at West Hartlepool When built 1871 - 4

By whom built Denton Owners Johnston & Co

Port belonging to Montrose Destined Voyage Baltic

If Surveyed Afloat or in Dry Dock In Dry Dock

Last Survey, No. 124829

Port Liverpool

Classed

Years assigned.

Character in Register Book.

90 A1

3.74

REPAIRS, OR EXAMINATION AS PER RULE

Damage

On Starboard Side, one bent plate of sheerstrake & one of topside batten down & replaced with new, one bent plate on Port side & one in bow batten down reset & replaced, fractured frame strengthened with 4 ft. angle at back part, 8 hold beams strengthened with 10 x 5/8 plates fitted on top, 4 new angles fitted to do. Deck bulkhead fore & aft. keel scraped & coated with paint & black varnish. Special Survey No. 1 for Iron Ships Limber boards taken up man hole covers batten off of water ballast tanks, strake of ceiling batten up in bowl buntlers, keel scraped clean inside & out, both surfaces of outside plating exposed excepting in way of cement, all found firm & good.

Present Condition of the

Decks Good

Waterways Good

Comings Good

Upper Deck Beams & Fastenings Good

Lower Deck Beams & Fastenings Good

Planksheers

Sheerstrakes Good

Topsides Good

Wales Good

Plank (Bottom) and Counter Good

Engine Room Skylights Good Coal Bunker, Openings, Lids, &c. Good Scuppers Good Cargo and Main Hatchways Good Hatches Good

General Observations, Opinion as to Class, &c. Has now been specially surveyed under the Rules Survey No. 1 for Iron Ships. Is now in a good & efficient state fit for the safe conveyance of dry & perishable goods to & from all parts of the World & may in my opinion be continued Classed 90 A1

S.S. Apl. No. 1-75

Treenails Good

Breasthooks and Stems Good

Transoms, Pointers, and Crutches Good

Timbers of the Frame at the openings Good

Ditto Ditto at other places Good

Keelsons Good

Clamps and Shelves Good

Ceiling Good

Rudder Good

Copper When put on

Caulking of Bottom, Deck, & Waterways Good

Windlass and Capstan Good

Pumps Good

Boats Good

Masts, Yards, &c. Good

Condition, how ascertained From Deck

Sails Good

Anchors No. of 3 Bower, 1 Stem, 2 Kedge

Cables Good

Hawsers and Warps 9-7-4 1/2-7 1/2-4 Good

Standing & Running Rigging Good

The Amount of Entry Fee ... £ 2 : 0 : 0 received by me, S.P.

Special ... £ 3 : 3 : 0 9 April 1875

Certificate (if required) ... £ : :

(Travelling Expenses, if any, £)

Committee's Minute 13th April 1875

Character assigned

90 A1

S.S. No. 1-75

Dep 75

Surveyor to Lloyd's Register of British and Foreign Shipping.



© 2019

Lloyd's Register Foundation

IRON461-0019