

# REPORT of SURVEY for REPAIRS, &c.

14311

No. 3/5/75

No. in Reg. Book. No. 11,089 Survey held at Sunderland Date, first Survey March 24<sup>th</sup> Last Survey March 29<sup>th</sup> 1875

419 on the Screw Steamer "John Johnsson" Master M. Lucock

Tonnage 500 built at Newcastle When built 1870 - 5 Mo

By whom built Mitchell Owners J. Johnsson 18 Leaden Hall Street London

Port belonging to London Destined Voyage Coasting

If Surveyed Afloat or in Dry Dock Siney's Shipway

Last Survey, No. 12284 Port London Iron

Classed A 1 Years assigned. 4 Character in Register Book. 72

## REPAIRS, OR EXAMINATION AS PER RULE Survey No. 1

*Now done, The vessel placed upon blocks, and the outer surface of shell plating cleaned down; the Man-hole doors to Ballast-tanks in both holds removed, & a good deal of the ceiling removed and repaired; the cement upon the inner surface of the bottom plating examined & tested & found sound and adhering satisfactorily to the iron. One plate forward, on the Starb. side, renewed, and 18" on the port side removed, made fair and refitted; several rivets in the bottom on each side, and a few keel rivets, aft, renewed; Cement in way of new rivets renewed, & the Blow-off and Duction cocks refitted; a part of the ceiling renewed; Bilge keel on each side and Hatches repaired, and the outer surface of shell plating coated with paint.*

Present Condition of the	Good	Fair	Poor	Witches	Good
Decks				Windlass and Capstan	
Waterways	"			Pumps Metal	Good
Comings	"			Boats 3 H.	
Upper Deck Beams & Fastenings	"			Masts, Yards, &c. Ex. where where	
Lower Deck Beams & Fastenings	"			Condition, how ascertained	
Planksheers	"			Sails	Seen
Sheerstrakes	"			Anchors No. of 3 B. 15 LK	and
Topsides	"			Cables	
Wales	"			Hawsers and Warps	Sufficient
Plank (Bottom) and Counter	"			Standing & Running Rigging	
Engine Room Skylights	Good				
Coal Bunker, Openings, Lids, &c.	Good				
Scuppers	Good				
Cargo and Main Hatchways	Good				
Hatches	Good				

General Observations, Opinion as to Class, &c.

*This vessel is now in good and efficient state of repair and eligible in my opinion to remain as classed A.T., and to be marked in the Register Book S.P.W. 1. 51d/75*

The Amount of Entry Fee ... £ : : received by me, AW

Special ... £ 2 : 2 : - 25<sup>th</sup> April 1875

Certificate (if required) ... £ : 5 : -

(Travelling Expenses, if any, £ )

Committee's Minute 4<sup>th</sup> May 18 75

Character assigned Fe

S.P.W. 1. 51d/75

JBW

Surveyor to Lloyd's Register of British and Foreign Shipping.