

REPORT of SURVEY for REPAIRS, &c.

14370.

Key 6/5-75

No. in Reg. Book. **No.** 3453 Survey held at West Hartlepool Date, first Survey 21st April Last Survey 20th April 1875
439 on the Low St. Marmora Master Staniland
 Tonnage 649 built at Hartlepool When built 1868 - 3 mo
 By whom built Denton Owners J. Horsfield & Co.
 Port belonging to Hartlepool Destined Voyage Baltic
 If Surveyed Afloat or in Dry Dock In Dry Dock

Last Survey, No. 12623. Port Liverpool Classed 4-74
 Years assigned. 4-74 Character in Register Book. A1

REPAIRS, OR EXAMINATION AS PER RULE Special Survey No. 2 Iron Ships S.S. Apr No. 1-70.
Four hold beams strengthened with plates on the 10+5/8 riveted to double angles,
keel scraped clean inside & out, coated with Paint & black varnish, cement
in flat made good where necessary,

Also now been specially surveyed under the Rule Survey No. 2 for Iron
ships, Limber board taken up, man hole covers taken off, waterballast
tanks, the strakes of keeling plank lifted in fore hold keel scraped
clean inside, cement examined, chain cables up & ranged for inspection
Windlass examined (Patent), all found firm & good.

Present Condition of the
 Decks Good
 Waterways Good
 Comings Good
 Upper Deck Beams & Fastenings Good
 Lower Deck Beams & Fastenings Good
 Plank sheers Good
 Sheerstrakes Good
 Topsides Good
 Wales Good
 Plank (Bottom) and Counter Good
 Engine Room Skylights Good Coal Bunker, Openings, Lids, &c. Good Scuppers Good Cargo and Main Hatchways Good Hatches Good
 General Observations, Opinion as to Class, &c. Is now in a good & efficient state fit for the safe
conveyance of dry perishable goods to & from all parts of the World &
may in my opinion be continued Classed A1
S.S. Apr No. 2-75

Treenails Good
 Breasthooks and Stomps Good
 Transoms, Pointers, and Crutches Good
 Timbers of the Frame at the openings Good
 Ditto Ditto at other places Good
 Keelsons Good
 Clamps and Shells Good
 Ceiling Good
 Rudder Good
 Copper Good When put on Good
 Caulking of Good
 Bottom, Deck, & Waterways Good
 Windlass and Capstan Good
 Pumps 3 & Good
 Boats 3 & Good
 Masts, Yards, &c. Good
 Condition, how ascertained From Deck
 Sails Good
 Anchors No. of 3 Bowers / Stern 2 / 12 lbs
 Cables 2 5/8 Patmans 1 1/2
 Chain 60 ft 1/2 in
 Hawseers and Warps 11-8 1/2 - 3 1/2 - 5
 Standing & Running Rigging Good

The Amount of Entry Fee £ 2 : 0 : 0 received by me, 10/4
 Special £ 3 : 3 : 0 3 May 1875
 Certificate (if required) £ : :
 (Travelling Expenses, if any, £)

Committee's Minute 7th May 1875

Character assigned A1
S.S. No. 2-75
J.W.

Surveyor to Lloyd's Register of British and Foreign Shipping.