

REPORT of SURVEY for REPAIRS.

14430

No. in Reg. Book. No. Survey held at London Date, first Survey 28 Dec 1872 Last Survey 1 Feb 1873
 on the win Tarr M Thames Master A Hyde
 Tonnage 157 built at Stambarton When built 1871. 3 mo.
 By whom built M. Gillian Owners Semperley's Co
 Port belonging to London Destined Voyage Montreal
 If Surveyed Afloat or in Dry Dock On the Victoria Dock Pontoon and afloat
 Last Survey, No. 14429 Port Loon Classed 100 A

REPAIRS, &c.

Caulked weather deck all fore and aft.
 Steering-gear refitted, and supplied new propeller.
 Added a stringer in tween decks (about thirty-inches down from gunwale), extending for three-fifths length amidships, composed of double angle irons of $4 \times 3 \frac{1}{2} \times 9 \frac{1}{2}$, having a bulb-plate $7 \times 7 \frac{1}{2}$ between them, and riveted to double lugs on the main frames.
 Bottom cleaned, and coated with Paint and allum.

Present Condition of the

Decks	Treenails	Windlass and Capstan	<u>Good</u>
Waterways	Breasthooks and Stemson	Pumps	<u>Good</u>
Comings	Transoms, Pointers, and Crutches	Boats	<u>Good</u>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.	<u>Good</u>
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained	<u>Seen from the deck</u>
Planksheers	Keelsons	Sails	<u>Good</u>
Sheerstrakes	Clamps and Shelves	Anchors No. of	<u>3 Good</u>
Topsides	Ceiling	Cables	<u>and</u>
Wales	Rudder	Hawsers and Warps	<u>Sufficient</u>
Plank (Bottom) and Counter	Copper <u>Leant</u> When put on <u>1871</u>	Standing & Running Rigging	<u>Good</u>
Engine Room Skylights <u>Good</u>	Caulking of <u>3 good where</u>	Cargo and Main Hatchways <u>Good</u>	Hatches <u>Good</u>
Coal Bunker, Openings, Lids, &c. <u>Good</u>	Bottom, Deck, & Waterways <u>Examined</u>		

General Observations and Opinion,
Ship in good, and efficient condition, and in my opinion eligible to remain as classed.

A. H. Barnes

The Amount of Entry Fee.....£..... is received by me,

Special.....3:3:.....

Certificate (if required) - - -

Committee's Minute

18

Character assigned



© 2019

Lloyd's Register Foundation