

REPORT of SURVEY for REPAIRS, &c.

14713

Dec 8/6/75

No. in
Reg. Book.

No. 11133

Survey held at Sunderland Date, first Survey May 3rd Last Survey May 29th 1875.

283

on the

Sr. "Dione"

Master

R. Lucock

Tonnage

537
413
469

built at

Stockton

When built

1868. (3 mo)

By whom built

Richardson

Owners

J. Johnasson

18 Seadenhall Street, London E.C. 4

Port belonging to

London

Destined Voyage

If Surveyed Afloat or in Dry Dock

South Graving Dock

Classed

Years assigned.

Character in Register Book.

B

11.7.4

Last Survey, No.

13441

Port

London Iron

REPAIRS, OR EXAMINATION AS PER RULE

Annual Survey

Keel and Bottom examined, Caulked a few Butts of Bilge plating, and Renewed one Plate of fairboard (broken) Starboard side near Fore-foot; removed two plates of Bulwarks St^a Bow and refitted the same after passing through the Rolls; Raised the "Anchor" Forecastle in height; Shifted Fore Hatch two spaces of Beams farther aft; beams in old Hatchways repaired by Scarphs 2 ft in length; Boiler removed Iron Work both inside and outside thoroughly cleaned and examined. Man Holes in Tanks removed Frames Floors and Cement where seen good; Bottom payed with Black Varnish remainder of Iron Work

please J. Over.

Present Condition of the

Decks

Good

Thwarts

Rivets

Good

Windlass and Capstan

Good

Waterways

4

Breasthooks and Stenson

4

Pumps

4

Comings

4

Transoms, Pointers, and Crutches

11

Boats

3 No

4

Upper Deck Beams & Fastenings

4

~~Timbers~~ of the Frame at the openings

4

Masts, Yards, &c.

4

Lower Deck Beams & Fastenings

4

Ditto Ditto at other places

where seen

Condition, how ascertained inspⁿ from DR

Planksheers

4

Keelsons

Do

Sails

✓

Sheerstrakes

4

Clamps and Shelves

Good

Anchors No. of 3 B. 1 S. 2 K. good

Topsides

4

Ceiling

4

Cables

✓

Wales

4

Rudder

4

Hawsers and Warps

✓

~~Plank~~ (Bottom) and Counter

4

Copper Blacking When put on

now

Standing & Running Rigging

good

Engine Room Skylights

good

Coal Bunker, Openings, Lids, &c.

good

Scuppers

good

Cargo and Main Hatchways

good

Hatches good

General Observations, Opinion as to Class, &c.

She is now in good and efficient condition and fit in my opinion to remain as Classed. Vir. B. 1.

Engine Certificate attached.

The Amount of Entry Fee£

received by me,

Special

... ..£

4 : 4 : 0

3rd June 1875

Certificate (if required)

... ..£

5 : -

(Travelling Expenses, if any, £)

Committee's Minute

11th June

18

75

Character assigned

B

Joseph New

Surveyor to Lloyd's Register of British and Foreign Shipping.



© 2019

Lloyd's Register Foundation

IRON462-0096

work both inside and outside painted.

When the Boiler was removed the frames
floors, boiler seating, Rivets and Cement, were
carefully examined and found in good condition
the lower parts of the Coal Bunker Bulkheads
in this neighbourhood repaired; the Deck in
way of Fore Hatch repaired and part of
that in ways of Engine and Boiler Room
renewed with Yellow pine.

Joseph Keen.