

Row N^o 14957

Report of Survey for Repairs of Engines and Boilers.

No. _____ (Recd 10. 11. 75)
No. in Reg. Book. Survey held at London Date, first Survey _____ Last Survey Apr 1875
966. on the Engines and Boilers of S.S. Melpotamia Tons 121 1/2
Built London 1871
Owners Lynch & Co. Port belonging to London Classified _____ Years assigned. _____ Character in Register Book. 907-1

Diameter of Cylinders 30" x 60" Engines made at Thames When made 1871
Length of Stroke 23 1/2"
Pressure of Steam 60 lbs By whom made Anderson, Colburn & Co
Nominal Horse Power 160

Particulars of Repairs and Examination

The vessel placed in the dry dock and stern tube, propeller, shaft and all connections examined and found in good condition

Pistons, slide valves, circulating, and air pumps overhauled. New brass valve seat fitted. Circulating pump, and new rubber valves put in pumps where necessary. All the working parts of machinery overhauled and adjusted.

Some caulking done to boilers and six new tubes fitted.

The Machinery and Boilers of this vessel are now in good order and safe working condition and in my opinion eligible to run as certified in the Register Book

(Condition of Engines and Boilers, and subsequent Repairs and Examinations, to be clearly stated.)


(The Surveyors are requested not to write on or below the space for Committee's Minute).

The Amount of Fee ... £ 5 : 5 : received by me, 29 Nov 1875
Certificate (if required) ... £ - : - :
(Travelling Expenses, if any, £)

Committee's Minute

Record Lloyd's Reg. 11, 75

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



Lloyd's Register Foundation