

* 15051

Report of Survey for Repairs of Engines and Boilers.

(Ref 11.12.73)

No.

No. in
Reg. Book.

Survey held at

London

Date, first Survey

Last Survey

1875

904

on the

Machinery and Boilers of S.S. Menzaleh

Tons

161

Owners

Shaw & Co

Port belonging to

London

Classed

Character in Register Book.

904

Diameter of Cylinders 31" 38"

Length of Stroke 33"

Pressure of Steam 65 lbs

Nominal Horse Power 130

Engines made at

North Shields

When made

YEAR.

1870

By whom made

N. Eastern Engineering Co.

Particulars of Repairs and Examination

High & Low pressure pistons examined
Low pressure cylinder bored out. New packing ring
in high pressure piston. Slide valves overhauled.
Circulating, air, bilge & feed pumps examined.
Sew rubber valves put in circulating and air
pumps where required. One of the donkey suction
pipes disconnected and blind flange put on, to
prevent water being run unintentionally from the
Sea into the bilge. The vessel placed in the
dry dock and stern tube, shaft, propeller and
all connections examined.

An additional stay put in dome of port
boiler. Boilers repaired and thoroughly cleaned
and put in good order.

The engine and Boilers of this vessel are
now in good order and safe working condition and in
my opinion eligible for the notification Lloyd's M Co
in the Register Book

The Amount of Fee ... £ 5 : 3 :

Certificate (if required) ... £ :

received by me,

18/12 1875

(Travelling Expenses, if any, £)

Committee's Minute

record

7th Feby 1876

Progr. M.C. 12.75

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



© 2019
Lloyd's Register
Foundation

(The Surveyors are requested not to write on or below the space for Committee's Minute).

1200463-0032