

Don \*15466

34865

# Report of Survey for Repairs of Engines and Boilers.

(Recd. 24. 7. 75)

No. in Book. Survey held at London Date, first Survey June 14<sup>th</sup> Last Survey July 23<sup>rd</sup> 1875

22 on the Screw Steamer Timor 1440 Tons

Owners Nelson Donkin & Co Port belonging to London Classified 100 A1 Years assigned. Character in Register Book.

Diameter of Cylinder 36 & 68 inches Engines made at London When made 1874

Length of Stroke 45 inches Pressure of Steam 65 lbs per sq in By whom made Maudslay & Co

Nominal Horse Power 200

Particulars of Repairs and Examination Crank Shaft examined on June 14<sup>th</sup>, flaw discovered in after bearing of forward engine, extending for a distance of about 9 inches, and being of a very dangerous nature; Recommended a new Crank Shaft to be fitted. Pistons, Slide Valves, Pumps and other working parts thoroughly overhauled, The Boilers scaled and cleaned inside and out, new Crank shaft fitted, and Engines tried under steam on 23<sup>rd</sup> of July and everything working well. The machinery and boilers of this vessel are now in good order and in good working condition. It is respectfully submitted for the Committee's consideration that this vessel is eligible to have the notification Lloyds M.C. recorded in the Register Book, and to have a Certificate granted from the 23<sup>rd</sup> of July 1875.

The Amount of Fee ... £ 44 4 0 received by me,

Certificate (if required) ... £ - : - : - } 31<sup>st</sup> July 1875

Travelling Expenses, if any, £

Committee's Minute 6<sup>th</sup> August 1875

William Parker

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

received Lloyds M.C. 7. 75

W.P.



© 2019

Lloyd's Register

Foundation

120N464-0120