

REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. **No.** Survey held at London Date, first Survey Oct 25 Last Survey Dec 6 1875

on the S. Nagpore Master _____
 Tonnage under Tonnage Deck 1141.01 Built at Glasgow When built 1863 YEAR. MONTH.
 Ditto of Spar Deck, or Avoing Deck _____ Owners W Rome Port belonging to Liverpool
 Ditto of Poop, or Raised Q. Dk. 63.68 Residence _____
 Ditto of Houses on Deck 1.36 By whom built Barclay Destined Voyage Calcutta
 Ditto of Forecastle _____ If Surveyed Afloat or in Dry Dock Pontoon
 Gross Tonnage 1209.05
 Crew Space, as per Rule _____
 Register Tonnage, out on Beam 1205.05
 Engine Room _____
 Reg. Tons as St mer, out on Bm. _____

Length of Poop 53 ft. Ditto, Forecastle 36 ft. Ditto, Raised Quarter Deck _____ ft. Years assigned. Character in Register Book.
 Last Survey, No. 11990 Port Iron Classed *A1 9.72
S.S. No. 3-75

REPAIRS, OR EXAMINATION AS PER RULE

At the present time the vessel placed on the Pontoon, the hull cleared and all the close wood ceiling taken up on both sides all fore and aft exposing both surfaces of plating &c examined and found good. Scraped, shipped or beaten clean both inside and outside. Outside plating drilled in various places and found to be in a satisfactory condition, little or no waste perceptible. Cement tested which was adhering firmly to the iron, but being worn and thin in many places has been thickened and recemented. All new ceiling. Painted and coated inside and outside.

The Chain Cables were on deck & examined in 1872 as per Liverpool Report 23462, & New Windlafs at the same time. Part shipped & unshipped new.

Present Condition of the					
Decks	Good	Freemails	Runts	Good	Windlass and Capstan
Waterways	"	Breasthooks and Stemson	"	"	Pumps
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	"	Masts, Yards, &c.
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	"	Condition, how ascertained
Planksheers	"	Keelsons	"	"	Sails
Sheerstrakes	"	Clamps and Shelves	"	"	Anchors No. of 3 Bbs. & 8 Shelves
Topsides	"	Ceiling	"	"	Cables
Wales	"	Rudder	"	"	Hawsers and Warps
Plank (Bottom) and Counter	"	Copper Painted & When put on	New	"	Standing & Running Rigging
Engine Room Skylights	"	Caulking of	"	"	Cargo and Main Hatchways
Coal Bunker, Openings, Lids, &c.	"	Bottom, Deck, & Waterways	Good	"	Hatches
General Observations, Opinion as to Class, &c.					

She is now in an efficient state of repair and entitled to remain as before and marked in the Register Book

S.S. No. 3-1875

Senhouse Martindale

The Amount of Entry Fee ... £ ... : : received by me, H. W. Hill Dec 1875
 Special ... £ 6 : 6 :
 Certificate (if required) ... £ ... : 5 :
 (Travelling Expenses, if any, £ ...)

Committee's Minute 7th December 1875

Character assigned T.S.W. S.S. No. 3-75

Surveyor to Lloyd's Register of British and Foreign Shipping.