

REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. **No. 4195** Survey held at Glasgow Date, first Survey 3^d March Last Survey 7 March 1876
Sup 64 on the S.S. Amelia Master Campbell

Official Number 7379
 TONNAGE under Tonnage Deck 481
 Ditto of Spar Deck, or Awning Deck
 Ditto of Poop, or Raised Qr. Dk.
 Ditto of Houses on Deck
 Ditto of Forecastle
 Gross Tonnage 460
 Crew Space, as per Rule
 Register Tonnage, cut on Beam
 Engine Room
 Reg. Tons as St^rmer, cut on Bm. 380
 Built at Port Glasgow When built 1875-10
 Owners A. S. Seligmann Port belonging to Glasgow
 Residence 29 St Vincent Place
 By whom built Murray Destined Voyage Sanwich
 If Surveyed Afloat or in Dry Dock Afloat

Length of Poop 47 ft. Ditto, Forecastle 30 ft. Ditto, Raised Quarter Deck — ft. Years assigned. 100 A.S.
 Last Survey, No. 15794 Port Iron Character in Register Book. 2-7-6

REPAIRS, OR EXAMINATION AS PER RULE For Damage
Single angle iron hold beams in main hold all removed
set fair and replaced, the hatchway beams doubled with
4 x 3 x 7/16 angle irons, the other beams and half beams doubled with
4 x 3 x 7/16 angle irons. Hatchway carlings removed of 6" bulk iron
a pair of tie plates added 9 1/2 x 7/16. Lower deck relaid. Stanchions
refitted

Present Condition of the					
Decks	Good	Repairs	Rebuilt	Good	Windlass and Capstan
Waterways	"	Breasthooks and Stemson			Good
Comings	"	Transoms, Pointers, and Crutches			Pumps
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings			Boats
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places			Masts, Yards, &c.
Planksheers	"	Keelsons	When		Condition, how ascertained
Sheerstrakes	"	Clamps and Shelves			Sails
Topsides	"	Ceiling			Anchors No. of
Wales	"	Rudder			Cables
Plank (Bottom) and Counter	Not seen	Copper	When put on	Good	Hawsers and Warps
Engine Room Skylights	Good	Caulking of			Standing & Running Rigging
Coal Bunker, Openings, Lids, &c.	Good	Bottom, Deck, & Waterways	Good		Sufficient
General Observations, Opinion as to Class, &c.		Scuppers	Good		Cargo and Main Hatchways
					Good
					Hatches
					Good

This vessel is now in good condition and in my
opinion eligible to remain as Classed.

The Amount of Entry Fee ... £ ... received by me, }
 Special ... £ ... }
 Certificate (if required) ... £ ... }
 (Travelling Expenses, if any, £ ...)
 Committee's Minute 14th March 1876
 Character assigned 100 A.S.

Lawrence
 Surveyor to Lloyd's Register of British and Foreign Shipping.
 © 2019
 Lloyd's Register Foundation