

16166

Report of Survey for Repairs of Engines and Boilers.

No. in Book. Survey held at London Date, first Survey 27 March Last Survey 11 April 1876
 on the S.S. Peninsula 377 Tons
 Owners J Hall & Co Port belonging to London Classed No Class Years assigned. Character in Register Book.

Diameter of Cylinder 30" Engines made at London When made 1855
 Length of Stroke 18"
 Pressure of Steam 30 lb. By whom made J Penn & Son Greenwich
 Nominal Horse Power 80

Particulars of Repairs and Examination. Engines Thoroughly examined overhauled and all working parts adjusted. Three way Cock. Connecting sea and bilge suction with Dumble pump so arranged that a direct connection between the sea and bilge could be opened by accident. This Cock condemned and new one made and fitted in such a manner that it would be impossible for such an accident to occur. Boilers Thoroughly repaired 16 new tubes 6 new stays and plates in vicinity of man hole down repaired and strengthened.

Amount of Fee ... 12/4/76 ... £ 2 : 2 : 0 received by me, Certificate (if required) ... £ : : 13 Apr 1876

Wm William Parker
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

