

16241 Iron.

in the bows forward and about the bulkhead, a strong beam of semi-box form has been fitted abast the collision bulkhead and secured to the double angle iron stringers in hold and the adjacent frames by deep knee plates and gusset plates; all slack rivets have been cut out and renewed; the ceiling relaid; and the vessel in all other respects put into good and efficient condition. The bottom outside has also now been scraped and painted.

R. F. Reed.

Committee's Minute 12th May, 1876

Character assigned

907A
S.S. 1876-77
J.W.



© 2019

Lloyd's Register
Foundation