

16585

35533

Report of Survey for Repairs of Engines and Boilers.

No. _____
 No. in Reg. Book. Survey held at 11 over Date, first Survey _____ Last Survey 19th June 1876

174 on the Screw Steamer "The Lady" Carmichael Tons _____

Owners Submarine Telegraph Co Port belonging to London Years assigned. _____ Character in Register Book. 90 A1
 Classified 5.71

Diameter of Cylinder 34 Four Engines made at Glasgow When made 1871
 Length of Stroke 48
 Pressure of Steam 25-lb By whom made J. J. Thomson
 Nominal Horse Power 165

Particulars of Repairs and Examination New brass tube plate fitted to condenser, 500 (about), new tubes to do, the Outer bearings of paddle shaft relined and adjusted, Air pumps, new valves & repacked, Centrifugal Circulating pump new disc and shaft of gun metal, Donkey fitted with new piston & rings and repaired. All working parts overhauled and put in good order.
Restayed bottom of boiler, patched furnaces and combustion chamber, new stay plates in uptake.
The whole of the machinery and boilers are now in good order and safe working condition

The Amount of Fee ... 20/6 £ 3 . 3 : 0 . received by me, Wm. Parler
 Certificate (if required) ... £ : : 5 July 1876
 (Travelling Expenses, if any, £ 2 . 10 . 0 .)
 Committee's Minute 20th June 1876
Glasgow

