

# Report of Survey for Repairs of Engines and Boilers.

No. 16733  
 No. in Reg. Book. 1444 Survey held at London Date, first Survey 23<sup>rd</sup> June Last Survey Aug<sup>r</sup> 2<sup>nd</sup> 1876  
 on the S.S. "Dahlia" Tons 1304  
1425  
 Owners Harper Ferguson Jackson Port belonging to London Years assigned 100 A 1  
 Character in Register Book. 3. 15  
 Diameter of Cylinders 21" and 41" Engines made at Liverpool When made 1872  
 Length of Stroke 34<sup>in</sup> Pressure of Steam 70 lbs By whom made Geo. Forrester & Son  
 Nominal Horse Power 200

Particulars of Repairs and Examination. The Engines of this Vessel have undergone a thorough overhaul, new high pressure piston fitted & working parts where worn refaced or renewed where necessary.

Boilers repaired where worn & leaky. Ample Irons at front part of furnaces where deteriorated renewed, new pieces of furnace plate let in at Back ends where necessary, bottom part of main Ample iron securing cylindrical part of Shell to fronts rivetted, all tubes taken out and new Iron ones fitted.

Bilge injection altered to prevent unintentional connection between Sea & Bilge.

The Machinery of this Vessel is now in good & safe working condition and in my opinion eligible to have the notification Lloyd's M.C. in the Register Book and a Machinery certificate from date of last Survey.

The Amount of Fee ... 18/7.6 £ 5 : 5 : 0 received by me, G. W. Manuel  
 Certificate (if required) ... £ : : 15 Aug 1876

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

18