

18364 Iron
Barque No 67 "Brosfield"
Lower Masts & Bowsprit

Foremast 41'0" Diam^r 26" at partners and 18" at head

Main " 42.8 " 26" " " 18" " "

Bowsprit 34.0 " 24", 19" & 16" at head

3 angles in fore & main masts 3" x 3 1/2" x 6 1/16"

Seams lapped, rivetted with 3/4" rivets. Butts flush with straps double & treble rivetted

Plates. Fore mast 11'6" long x 5/16" & 6/16" thick

" Main " 11.6 " x 5/16" & 6/16 " "

" Bowsprit 11.6 " x 5/16" & 6/16 " "

Makers of Plates for Masts & Bowsprit

Mess^{rs} The Stockton Malleable Iron Co

Stockton on Tees

Mizen Mast of Pitch Pine 45' long 16 1/2" at wedgings

Lower Yards.

Fore & Main 68'0" x 14" Plates 4/16" & 3/16" thick

with 2 angle irons 2 1/4" x 2 1/4" x 1/4" for the whole length.

Seams & butts lapped. Doubling plate in middle.

Makers of iron for yards

Mess^{rs} The Bowersfield Iron Co

Stockton on Tees



Ed. J. M. A.



© 2019

Lloyd's Register
 Foundation

IRON471-0458