

REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. **No. 25573** Survey held at **Liverpool** Date, first Survey **3 March** Last Survey **10th April** 1877
 177 on the S. "Fiji" Master **J. Brown**
 TONNAGE under Tonnage Deck **1330** Built at **Belfast** When built **1875** YEAR. MONTH.
 Ditto of Spar Deck, or Avoing Deck
 Ditto of Poop
 Ditto of Raised Qr. Dk.
 Ditto of Houses on Deck
 Ditto of Forecastle
 Gross Tonnage **1471** Owners **R. J. Myers & Co** Port belonging to **Liverpool**
 Crew Space, as per Rule
 Register Tonnage, cut on Beam **1407** Residence **Liverpool**
 Engine Room By whom built **Harland** Destined Voyage **Melbourne**
 Reg. Tons as St^rmer, cut on Bm. If Surveyed Afloat or in Dry Dock **Landon G. Dk**

Length of Poop **✓** ft. Ditto, Forecastle **31 1/2** ft. Ditto, Raised Quarter Deck **31** ft. **See Book** Years assigned. **100 A 1** Character in Register Book. **12.75**
 Last Survey, No. **15425** Port **Iron** **Classed**

REPAIRS, OR EXAMINATION AS PER RULE **for Repair**
Now done

Nine pairs of short Pillars 2 1/2" dia fitted to beams of after house & three pairs of bracket plates at rounded top of same - Three pairs of bracket plates fitted to forecaskle stringer - three forecaskle beams doubled with 5 x 3 x 1/2 bars and an additional iron pillar fitted to forecaskle beam
 Bottom cleaned & painted

Present Condition of the

Decks good	Forecaskle Ribs good	Windlass and Capstan good
Waterways ✓	Breasthooks and Stemson ✓	Pumps ✓
Comings ✓	Transoms, Pointers, and Crutches ✓	Boats ✓
Upper Deck Beams & Fastenings ✓	Timbers of the Frame at the openings ✓	Masts, Yards, &c. ✓
Lower Deck Beams & Fastenings ✓	Ditto Ditto at other places ✓	Condition, how ascertained inspection
Planksheers ✓	Keelsons ✓	Sails complete
Sheerstrakes ✓	Clamps and Shelves ✓	Anchors No. of 3 B 15 2 H
Topsides ✓	Ceiling ✓	Cables complete
Wales ✓	Rudder ✓	Hawsers and Warps ✓
Bottom (Bottom) and Counter ✓	Copper Cement When put on 1875	Standing & Running Rigging good
Engine Room Skylights ✓	Caulking of ✓	Cargo and Main Hatchways good
Coal Bunker, Openings, Lids, &c. ✓	Bottom, Deck, & Waterways good	Hatches good
General Observations, Opinion as to Class, &c.	Scuppers good	

This vessel is now in good condition & eligible in our opinion to remain as classed

The Amount of Entry Fee ... **£ 2 : 2 : 0** received by me, **17/5 1877**
 Amou. Certificate (if required) ...
 Expenses, if any, £
 mittee's Minute **Liverpool May 1877.**
 Character assigned **100 A 1**

Geo. T. Cooper
 Surveyor to Lloyd's Register of British and Foreign Shipping.

Lloyd's Register Foundation

"Ziji" 25073



© 2019

Lloyd's Register
Foundation