

\*18593

# Report of Survey for Repairs of Engines and Boilers.

(Recd 11/6/99)

No. 202

No. in  
Reg. Book.

Survey held at

Hamburg

Date, first Survey

June

Last Survey

6 June 1877

840

on the Iron screw Steamer "Luxor"

Master

J. Benöke

Tons

1281  
847

Owners

"Kosmos" S. N. Co.

Port belonging to

Hamburg

Classed

Years  
assigned.

Character in Register Book.

90 A 1  
4, 73.

Diameter of Cylinders 29 1/2 x 59

Length of Stroke 3' 0"

Pressure of Steam 65 lbs

Registered Horse Power 130

Engines made at

Hartlepool

When made

1873

By whom made

Blair & Co.

## Particulars of Repairs and Examination

No repairs of importance have been found necessary on the Engines and boilers of this ship. The Engines have merely received a general and usual overhaul. All working parts like pistons slide valves, valve gearing, guides, pumps and shafting being found to be in very good condition and have merely been adjusted where found necessary. The after bush of the stern tube has however received new lignum vitae lining; the other parts of the stern tube as well as the propeller shaft were in a satisfactory state. The sea cocks and valves were repacked and adjusted while in dock.

The main boilers are in a first class condition and no repairs whatever besides cleaning were found necessary.

The same is to be said about the donkey boiler. I therefore beg to state that I consider the Engines and boilers of this vessel to be in a very good and safe working condition.

*[Large signature]*

The Amount of Fee ... £ 6-0-0 received by me,

Certificate (if required) ... £ : : 187

Travelling Expenses, if any, £

Committee's Minute

18

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

*[Signature]*



© 2019

Lloyd's Register  
Foundation

IRON 472-0242