

19360
REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. **No. 11454** Survey held at **Sunderland** Date, first Survey **Sept 15** Last Survey **Sept 18** 1877
271 on the **Screw Steamer "Vine"** Master **Schofield**
TONNAGE under Tonnage Deck
Ditto of Spar Deck, or Avning Deck
Ditto of Poop
Ditto of Raised Qr. Dk.
Ditto of Houses on Deck
Ditto of Forecastle
Gross Tonnage
Crew Space, as per Rule
Register Tonnage, cut on Beam
Engine Room
Reg. Tons as St'mer, cut on Bm. **424**
Built at **Hull** When built **1866** YEAR. MONTH.
Owners **E. Tatham** Port belonging to **Hull**
Residence **Hull**
By whom built **Earle** Destined Voyage **Not known**
Surveyed ~~Afloat~~ **Afloat** or in Dry Dock **of the River Wear Commission**
Length of Poop **ft.** Ditto, Forecastle **ft.** Ditto, Raised Quarter Deck **ft.** Years assigned. **5** Character in Register Book. **A 1**
Last Survey, No. **18334** Port **Hull Lion** **10. Gov. No 3 76** **5 77**

REPAIRS, OR EXAMINATION AS PER RULE **for damage**

Four shell plates on the Starboard flat bottom off furnished and made fair, and on examination found to be fit to replace. Broken frames cracked at a rivet hole compensated for by doubling pieces of angle iron of sufficient length and riveted to stows and shell plates. A large quantity of ceiling removed for examination of the cement which was at places disturbed and has been made good together with that required where the plates had been taken off. The ceiling replaced and the bottom coated as before. New steps fitted to the rudder.

Present Condition of the Decks good	Freeboards first good	Windlass and Capstan good
Waterways do	Breasthooks and Stemson do	Pumps do
Comings do	Transoms, Pointers, and Crutches do	Boats do
Upper Deck Beams & Fastenings firm	Timbers of the Frame at the openings do	Masts, Yards, &c. good
Lower Deck Beams & Fastenings do	Ditto Ditto at other places do	Condition, how ascertained from deck
Planksheers do	Keelsons good	Sails complete
Sheerstrakes do	Clamps and Shells do	Anchors No. of 3 B 10 2 lbs
Topsides do	Ceiling do	Cables not raised
Wales do	Rudder do	Hawsers and Warps good
Plank (Bottom) and Counter do	Copper do When put on do	Standing & Running Rigging good
Engine Room Skylights good	Caulking of Bottom, Deck, & Waterways good	
Coal Bunker, Openings, Lids, &c. good	Scuppers good	Cargo and Main Hatchways good
Hatches good		

General Observations, Opinion as to Class, &c. **This vessel being now in good and efficient condition is in my opinion eligible to remain in class**

The Amount of Entry Fee ... £ 2 : 0 : 0 received by me, **19 Sept 1877**
Special ... £ 1 : 1 : 0
Certificate (if required) ... £ 2 : 2 : 0
(Travelling Expenses, if any, £ ...)
Committee's Minute **25th September, 1877.**
Character assigned **A 1**

Surveyor to Lloyd's Register of British and Foreign Shipping.

© 2019

Lloyd's Register Foundation

IRON 474-0095