

REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. **No. 25798** Survey held at **Liverpool** Date, first Survey **Sept 7th** "Last Survey **Oct 3rd** 1877.
 122 on the Ship **"Theronese"** Master **Chapman**
 TONNAGE under Tonnage Deck **1319.** Built at **Belfast** When built **1855.**
 Ditto of Spar Deck, or Awning Deck
 Ditto of Poop
 Ditto of Raised Qr. Dk.
 Ditto of Houses on Deck
 Ditto of Forecastle
 Gross Tonnage **1811.** Owners **G. Duncan** Port belonging to **London.**
 Crew Space, as per Rule
 Register Tonnage, cut on Beam **1711.** Residence **London.**
 Engine Room
 Reg. Tons as St' mer, cut on Bm.
 By whom built
 If Surveyed Afloat or in Dry Dock **Queen's Dry Dock & Afloat.**
 Length of Poop ☒ ft. Ditto, Forecastle ☒ ft. Ditto, Raised Quarter Deck ☒ ft. Years assigned. **100 AL** Character in Register Book. **10.76.**
 Last Survey, No. **17303** Port **Simon** Classified **S.S. Shl No 3-74.**
 REPAIRS, OR EXAMINATION AS PER RULE **Repairs.**

Damage to cutwater by collision now effectually repaired - Bottom sighted, cleaned and coated with paint - Mizen Mast now renewed with iron, dimension as follows - Length 76 ft by 26" diameter 6/16 plates, with two plates at Mast head which are 7/16. Single irons 4 x 3 x 7/16, treble riveted butt straps at partners, seams single riveted, butts double riveted.

Present Condition of the	Good	Good	Good	Good
Decks	Good	Good	Good	Good
Waterways	Good	Good	Good	Good
Comings	Good	Good	Good	Good
Upper Deck Beams & Fastenings	Good	Good	Good	Good
Lower Deck Beams & Fastenings	Good	Good	Good	Good
Planksheers	Good	Good	Good	Good
Sheerstrakes	Good	Good	Good	Good
Topsides	Good	Good	Good	Good
Wales	Good	Good	Good	Good
Plank (Bottom) and Counter	Good	Good	Good	Good
Engine Room Skylights	Good	Good	Good	Good
Coal Bunker, Openings, Lids, &c.	Good	Good	Good	Good
Scuppers	Good	Good	Good	Good
Cargo and Main Hatchways	Good	Good	Good	Good
Hatches	Good	Good	Good	Good

This vessel being now in a good and efficient condition is eligible in my opinion to remain as Classed.

The Amount of Entry Fee ... £ : : received by me, }
 Special ... £ : : 22/10/77 }
 Certificate (if required) ... £ : :
 (Travelling Expenses, if any, £)
 Committee's Minute **Liverpool Oct 23 - 1877.**
 Character assigned **100 AL.**

Damage to L. 2. 2. 0 22/10/77

J. Shilstone
 Surveyor to Lloyd's Register of British and Foreign Shipping.
 © 2019
 Lloyd's Register Foundation
 IRON 474-0289

"Khersonese"
25498



© 2019

Lloyd's Register
Foundation