

*1996/

Report of Survey for Repairs of Engines and Boilers.

No. 25-888

No. in Reg. Book. Survey held at

Liverpool

Date, first Survey 28th Sept^r Last Survey 19th Dec^r 1877

207 on the

S.S. Orchis

Master H. Bowles

Tons 1138-1765-1712

Owners

Wm Johnston & Co

Port belonging to

Liverpool

Classed

Years assigned.

Character in Register Book.

100 A 1.

Diameter of Cylinders 1 of 34" - 1 of 60"

Length of Stroke

59"

Engines made at

Glasgow

When made

1870

Pressure of Steam

75 lbs.

By whom made

J Howden & Co

Registered Horse Power

200

Particulars of Repairs and Examination

A new high pressure cylinder has been fitted. One new high pressure slide valve fitted. Low pressure cylinder opened out piston overhauled. Crank shaft examined and found good. Air circulating feed and bilge pumps and valves overhauled. Sea cocks and chests overhauled. New crank pin braces fitted. New propeller fitted. The Boilers opened out. a number of Tubes removed scaled and cleaned. Two new spring safety valves fitted on each Boiler 4 3/8" diam. Tested under steam and found satisfactory.

The machinery and Boilers of this vessel are now in a good and efficient condition and in my opinion entitle the vessel to retain the notification Lloyd's M.C. 1877-12 mo.

The Amount of Fee ... £ 1 : 0 : 0 received by me,

Certificate (if required) ... £ : : 4/1 1878

(Travelling Expenses, if any, £

Committee's Minute.

Liverpool Jan^y 8th 1878.

100 A 1. Record Lloyd's M.C. in Rec^d Dec^r 77.

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

J. G. Kinghorn

Submitted that this vessel is eligible

Lloyd's Register Foundation

1
Cochis

25858



© 2019

Lloyd's Register
Foundation