

20267

Report of Survey for Repairs of Engines and Boilers.

No. 220.

No. in Reg. Book. Survey held at *Hamburg* Date, first Survey *12th Feb* Last Survey *14th Feb* 18*78**425* on the *S.S. Marianne Briggs* Master *Kitwood*Tons *630* Owners *Yorkshire Coal & L. Co.* Port belonging to *Goole* Years assigned. *90 A.1.* Character in Register Book. *2.77*Diameter of Cylinder *23¹/₂ x 44¹/₂* Engines made at *S. Shields* When made *1874*Length of Stroke *30¹/₂*Pressure of Steam *65 lbs*Registered Horse Power *80 H.P.* By whom made *J. Rodhead & Co*

Particulars of Repairs and Examination

The Engines and Boilers have been examined by me and I found it necessary that the Air and circulating pump, the valves and cocks on shipside, the bilge cocks and pipes had to be overhauled and well cleaned some of the bilge pipes had to be renewed, the Condensor had to be cleaned and the repacking of the tubes and 5 new tubes has to be made. Two new brackets on top of the Engine connected with the deck beam were broken and had to be renewed.

The Amount of Fee ... £ *1 : 1 :* received by me, Certificate (if required) ... £ *187*

(Travelling Expenses, if any, £)

Committee's Minute

18

J. A. Ribbert
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.