

# REPORT of SURVEY for REPAIRS, &c.

Survey held at London Date, first Survey 28 Jan<sup>r</sup> 1878 Last Survey 1 March 1878  
 on the S. City of Benares Master R. Jones  
 TONNAGE under Tonnage Deck 1186  
 Ditto of Spar Deck, or Avoing Deck  
 Ditto of Poop  
 Ditto of Raised Qr. Dk.  
 Ditto of Houses on Deck  
 Ditto of Forecastle  
 Gross Tonnage 1186  
 Crew Space, as per Rule  
 Register Tonnage, out on Beam  
 Engine Room  
 eg. Tons as St<sup>r</sup>mer, cut on Bm.  
 Length of Poop ft. Ditto, Forecastle ft. Ditto, Raised Quarter Deck ft.  
 Years assigned.  
 Character in Register Book.  
 Classed S.S. No 2. 75 7.75  
 Survey, No. 14748 Port London

REPAIRS, OR EXAMINATION AS PER RULE for S.S. No 3. Part Done.  
 Vessel put into dry dock and bottom scraped and painted.  
 The close ceiling in fore and after-holds entirely lifted and the cement  
 found to be in a good condition and closely adhering to the iron. The  
 surface of the iron in both the above named spaces freed from oxidation  
 and afterwards painted. The after peak cleared out and all oxidation  
 removed from the iron, the surface being afterwards painted. The outside  
 plating chipped free from rust and scale, both sides right fore and aft to  
 a little below the load water line. About a half of the close ceiling lifted is renewed with P. Pie.  
 The owners have made application to the committee to be allowed to  
 proceed on the intended voyage without completing the survey, and undertake to  
 do the remainder - viz: the main hold fore peak and chipping the scale  
 from three strakes of plating below the load water line - on the vessel's return.  
 (Letter attached hereto)

Present Condition of the	Good	Treenails	Rivets	Good	Windlass and Capstan	Good
Decks	Do	Breasthooks and Stenson		Do	Pumps	Do
Waterways	Do	Transoms, Pointers, and Crutches		Do	Boats	4 in No. Do
Platings	Do	Timbers of the Frame at the openings		Do	Masts, Yards, &c.	Do
Upper Deck Beams & Fastenings	Do	Ditto Ditto at other places		Do	Condition, how ascertained	From deck
Lower Deck Beams & Fastenings	Do	Keelsons		Do	Sails	Good
Stanchions	Do	Clamps and Shelves		Do	Anchors	No. of 3B. 1S. 2K
Strakes	Do	Ceiling		Do	Cables	Good where seen
Sides	Do	Rudder		Do	Hawsers and Warps	Good
Staircases	Do	Copper Paint When put on	now		Standing & Running Rigging	Do
Staircases	Do	Caulking of				
Staircases	Do	Bottom, Deck, & Waterways	Good			
Staircases	Do	Scuppers	Do			
Staircases	Do	Cargo and Main Hatchways	Do			
Staircases	Do	Hatches	Do			

General Observations, Opinion as to Class, &c.  
 She is now in a good and efficient condition and the Rules for S.S. No  
 have been partially complied with as stated above.  
 We are of opinion that she is eligible to remain as classed.

Amount of Entry Fee ... £ 5 : 5 :  
 Certificate (if required) ... £ 5 : 5 :  
 Surveying Expenses, if any, £  
 Committee's Minute 5th March 1878.  
 Character assigned  
 Note the case  
 W. L. C. M.  
 Surveyor to Lloyd's Register of British and Foreign Shipping.  
 © 2019 Lloyd's Register Foundation  
 IRON 476-0471