

*20438

Report of Survey for Repairs of Engines and Boilers.

(Recd 26.3.78)

No.

No. in
Reg. Book.

Survey held at

London

Date, first Survey

Last Survey March 15 1878

1261 on the S. S. Corinna

Master

Tons

697

Owners

J. Leuwick & Co

Port belonging to

London

Classed

Years
assigned.

Character in Register Book.

100A1

Diameter of Cylinder 30 1/2

Length of Stroke 33

Pressure of Steam 75 lb.

Registered Horse Power 190

Engines made at

Newcastle

When made 1870

By whom made

Palmer & Co

Particulars of Repairs and Examination

Blow off cocks removed from
ships bottom to turn of Belge,
Donkey Sea Suction
cock removed to above engine room platform,
Crank shaft examined, longitudinal flaw in main
bearing (not serious) Cylinders and Slide valves
examined and found good.

New Boilers fitted with mountings complete

Safety Valves set under steam.

New Safety valve to Donkey Boiler, loaded to 45
lbs per sq inch

The machinery and boilers are now in good
order and safe working condition, and render
the vessel eligible to have a machinery certificate
granted and Lloyd's M.C. 3.78 and N.B. 78 recorded
in the Register Book.

The Amount of Fee ... £ 9 : 10 : - received by me,

Certificate (if required) ... £ - : - : - 6 April 1878

(Travelling Expenses, if any, £)

Committee's Minute

29th March,

1878.

James T. Milner
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

(The Surveyors are requested not to write on or below the space for Committee's Minute.)

