

*20455-

Report of Survey for Repairs of Engines and Boilers.

(Dec 9. 3. 78)

No. 222 on the Screw Steamer "Despatch" Master
No. in Reg. Book. 222 Survey held at London Date, first Survey Feb 27 Last Survey March 5 1878
Tons 495 Owners J. Fenwick & Sons Port belonging to London Classified Years assigned 3.77 Character in Register Book A. 1

Diameter of Cylinder 25" x 48" Engines Comp. made at London When made 1845
Length of Stroke 30 By whom made Victoria Dock Eng Wks Co.
Pressure of Steam 75 lb.
Registered Horse Power 90

Particulars of Repairs and Examination Vessel placed on Pontoon, and sea connections and propeller examined, found shaft considerably down at outer bearing. On drawing the shaft to rebush stern tube it was found to be reduced in diameter from 8" to 7" by corrosion, recommended a new shaft to be fitted. This has been done and stern tube rebushed, propeller refitted, all sea cocks ground in.

In my opinion the vessel is eligible to remain as classed and to have a new machinery certificate granted from March 5th 1878

The Amount of Fee ... 13/3/78 ... £ 2 : 2 : 0 received by me, J.F.
Certificate (if required) ... £ - : - : 16 March 1878

(Travelling Expenses, if any, £)

Committee's Minute 15th March, 1878.

James Milton
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

It is submitted that she is eligible to remain as classed and to have a new Machinery Certificate granted
MP 8.3.78