

REPORT of SURVEY for REPAIRS, &c.

No. 25961

No. in Reg. Book. 16 on the SS "Fairfax" Survey held at Brixenhead Date, first Survey Feb 21st 1878 Last Survey March 11th 1878. Master W. Marshall

TONNAGE under Tonnage Deck 765
 Ditto of Spar Deck, or Awning Deck
 Ditto of Poop
 Ditto of Raised Qr. Dk.
 Ditto of Houses on Deck
 Ditto of Forecastle
 Gross Tonnage 930
 Crew Space, as per Rule
 Register Tonnage, cut on Beam
 Engine Room
 Reg. Tons as St^rmer, cut on Bm. 709

Built at Glasgow When built 1865 - 6
 Owners J. I. Sen Col C^t Port belonging to London
 Residence London
 By whom built London & Glasgow
 If Surveyed Afloat or in Dry Dock Mess^{rs} Clover's Dry Dock

Length of Poop - ft. Ditto, Forecastle - ft. Ditto, Raised Quarter Deck - ft.
 Years assigned. 90 A1.
 Character in Register Book. SS No 1/26.

Last Survey, No. 18755 Port Lion

REPAIRS, OR EXAMINATION AS PER RULE

Now done, Deck and wood planchies Caulked all fore and aft. Part new bridge houses at sides where carried away, and other small repairs to deck fittings where found damaged by stress of weather during her last voyage. One new boat.

In the bottom on the port side under a pump where the cement had broken away the plate was found badly wasted and leaky. And being in the middle of a plate in the inside course of plating, a four feet doubling piece the full breadth of the plating now fitted on the outside and the cement made good.

Present Condition of the			
Decks	Good & Caulked	Trunnels	Rivets good
Waterways	Good	Breasthooks and Stems	"
Comings	"	Transoms, Painters, and Crutches	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"
Planksheers	"	Keelsons	"
Sheerstrakes	"	Clamps and Shelves	"
Topsides	"	Ceiling	"
Wales	"	Rudder	"
Plank (Bottom) and Counter	"	Copper Cement	When put on 6/8/72/76
Engine Room Skylights	Good	Caulking of	
Coal Bunker, Openings, Lids, &c.	Good	Bottom, Deck, & Waterways	Good
General Observations, Opinion as to Class, &c.		Scuppers	Good
		Cargo and Main Hatchways	Good
		Hatches	Good
		Windlass and Capstan	Good
		Pumps	Good
		Boats	Good. One new.
		Masts, Yards, &c.	Good
		Condition, how ascertained	Seen on board
		Sails	Good and complete
		Anchors	No. of 303. 15. 27.
		Cables	Good (3" on deck)
		Hawsers and Warps	Good
		Standing & Running Rigging	Good

This vessel is now in good condition and in my opinion eligible to remain as Classed 90 A1.

The Amount of Entry Fee... £ 3 : 3 : 0 received by me, J. F. L.
 Certificate (if required) ...
 Travelling Expenses, if any, £
 Committee's Minute Liverpool March 15 1878.
 Character assigned 90 A1. Notice to Owners about Boilers.

J. F. Liphart
 Surveyor to Lloyd's Register of British and Foreign Shipping.
 Lloyd's Register Foundation

IRON 476-0544