

Report of Survey for Repairs of Engines and Boilers.

No. _____
 No. in Reg. Book. Survey held at London Date, first Survey 11th May Last Survey 15th May 1878
40 on the S. S. Neptune Master _____
532 Owners Tatham & Co Port belonging to Liverpool Classified _____
840 Years assigned. Character in Register Book. 100A1
2.78

Diameter of Cylinder 28 1/2 & 36 1/2 Engines made at Stockton When made 1873
 Length of Stroke 36 By whom made Blair & Co
 Pressure of Steam 65
 Registered Horse Power 130

Particulars of Repairs and Examination Air pump & circulating pump overhauled and new india rubber valves fitted where required. Feed pumps overhauled. High pressure cylinder opened out and piston springs examined. Main bearings and top end brasses adjusted. Both cylinders and valve chests recleaded with mahogany and brass straps. Boilers stripped and cleaned from old lagging and re coated with Silicate of cotton. Two new tubes fitted in boilers.

The machinery and boilers of this vessel are as far as seen in good order and safe working condition and in my opinion render the vessel eligible to remain as classed.

The Amount of Fee ... 16/5/78 ... £ 1 : 1 : 0 received by me, H. J. M. M. M.
 Certificate (if required) ... £ : : 16 May 1878

(Travelling Expenses, if any, £ _____)

James M. M. M.
 Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute _____ 18