

REPORT of SURVEY for REPAIRS.

Rev 1/6/78

No. in Reg. Book. **No. 132** Survey held at **Plymouth** Date, first Survey **13 Decr 77** Last Survey **14 Janz. 1878**
 on the **Amble Norman** Barque Master **A. Davidson**
849 Tonnage **822** built at **Glasgow** When built **1876**
 By whom built **Russell** Owners **Thos Cook & Co.**
 Port belonging to **London** Destined Voyage **China**
 If Surveyed Afloat or in Dry Dock **Afloat**

Last Survey, No. **19155** Port **Iron** Classed **100**

REPAIRS, &c.

This vessel on her voyage from London to this Port was shewn on her Beam ends carrying along Gal chain Rails. Topgal Rail, chain and topgal Bulwarks and iron Manekions. between Fore and chain rigging Rod chain Hatch. and back Manekions of 'stencil' deck. as after Beam of chain Hatch. Rod Deck House. Two Boats started and damaged part of Poop. and shained seams of deck - The damages had been repaired by fitting about 50ft of new chain Rail of spotted iron. new iron Bulwarks plates of which are less in width than those in original Bulwarks - and as there were diagonally fitted Manekions at every bulk in the Bulwarks - additional Manekions have been fitted to suit the lesser sized plates in Bulwarks - Shear of Deck on Deck Stringer plate has been lifted to admit of Manekions being riveted to the angle-iron along it - additional work has been fitted. Decks have been caulked when necessary. Boats. Deck Houses. Hatches and part of Poop have been repaired. and all other damages made good

Present Condition of the

Decks	Good	Treenails	Perish	Good	Windlass and Capstan	Good
Waterways	✓	Breasthooks and Stemson	✓	✓	Pumps	✓
Comings	✓	Transoms, Pointers, and Crutches	✓	✓	Boats	✓
Upper Deck Beams & Fastenings	✓	Timbers of the Frame at the openings	✓	✓	Masts, Yards, &c.	✓
Lower Deck Beams & Fastenings	✓	Ditto Ditto at other places	✓	✓	Condition, how ascertained	✓ by Carpenter
Planksheers	✓	Keelsons	✓	✓	Sails	fully equipped
Sheerstrakes	✓	Clamps and Shelves	✓	✓	Anchors	No. of 3 B. 1 P. 2 H.
Topsides	✓	Ceiling	✓	✓	Cables	full length edge
Wales	✓	Rudder	✓	✓	Hawsers and Warps	new good
Plank (Bottom) and Counter	✓	Copper	When put on	✓	Standing & Running Rigging	✓
Engine Room Skylights	✓	Caulking of	Bottom, Deck, & Waterways	✓	Cargo and Main Hatchways	Good
Coal Bunker, Openings, Lids, &c.	✓	Scuppers	Good	✓	Hatches	Good

General Observations and Opinion,

Vessel in good order again and fit to remain her class

The Amount of Entry Fee.....£ **none** :

is received by me,

Special..... **7: 7:**

Certificate (if required) **none** :

Committee's Minute

4th. June 1878.

Character assigned

100A

TRM



© 2019

Lloyd's Register

IRON477-0565