

REPORT of SURVEY for REPAIRS, &c.

No. in Reg. Book. **No. 145** Survey held at **Calcutta** Date, first Survey **20th April** Last Survey **26th April** 1878
625 on the **S.S. "Brazilian"** Master **Smith**
 Tonnage **880** built at **Newcastle** When built **1869**
 By whom built **Mitchell** Owners **J. Clapham & Co.**
 Port Belonging to **Newcastle** Destined Voyage **Coast & Bombay**
 If Surveyed Afloat or in Dry Dock **in dry dock**

Last Survey, No. **18655** **10th Month** 1876. Port **Newcastle** Classed **Years assigned** **Character in Register Book**
90 A1

REPAIRS, OR EXAMINATION AS PER RULE

This vessel having grounded on what is supposed to have been a heap of discharged stone ballast off the island of "Ranatur" in Salt's strait has been docked for examination as her bottom, when a few slack rivets being found (15 in all) in the bottom plating in midships have been removed and have been replaced by sound ones. 20 butts (9 in the starboard side and 11 on the port side) in the same vicinity were found very slightly weeping. These have been cemented, no rivets being started, and the vessel's bottom has been well coated with paint and tarred.

Present Condition of the

Decks good where seen	Treenails Rivetting good where seen	Windlass and Capstan in good order
Waterways guttering	Breasthooks and Stemson "	Pumps "
Comings "	Transoms, Pointers, and Crutches "	Boats all sound
Upper Deck Beams & Fastenings "	Timbers of the Frame at the openings "	Masts, Yards, &c. "
Lower Deck Beams & Fastenings "	Ditto Ditto at other places "	Condition, how ascertained by examination
Planksheers plating	Keelsons "	Sails 1 1/2 sails
Sheerstrakes "	Clamps and Shelves "	Anchors No. of 3 Bowers, 1 stream, 2 Kedges
Topsides "	Ceiling "	Cables 270 fms bower 90 fms stream
Wales "	Rudder good & well hung	Hawsers and Warps 6 assorted
Plating (Bottom) and Counter "	Copper Paint When put on April 1878	Standing & Running Rigging good
	Caulking of Bottom, Deck, & Waterways good	

Engine Room Skylights **good** Coal Bunker, Openings, Lights, &c. **good** Scuppers **good** Cargo and Main Hatchways **good** Hatches **good**.

General Observation, Opinion as to Class, &c. **A strong well built iron steamer, has in my opinion taken no hurt from the late grounding, and is fit to be retained on the Register as classed.**

The Amount of Entry Fee £ : : received by me, }
 Special £ L : 4 : 11/4 187 }
 Certificate if (required) £ : :
 (Travelling Expenses, if any, £)

Committee's Minute **4th June 1878**

Character assigned **90 A1**

W Stewart R.N.R.

Surveyor to Lloyd's Register of British and Foreign Shipping.

Port of Calcutta.
 The 10th May 1878.



© 2019

Lloyd's Register
 Foundation
 IRON477-0569