





21340. Iron.

engine and boiler room entirely renewed; the tank tops scraped and tared and cemented, and found tight and satisfactory; the whole of the ceiling lifted and relaid, part being renewed; two halfhead plates cut off and refitted, and the bottom inside, and the vessel inside in way of repairs scraped and painted, and the deck recaulked.

Opportunity has now been taken to meet the requirements of No 3 survey; the whole interior of the vessel, therefore, has now been properly scraped, and chopped where required, including the peaks and hunters, and repainted; the wales and topsides scraped and painted; several deck planks on each side renewed; the windlass unhooked and partly stripped and found good; the chain cables ranged and examined; the iron coamings round engine space partly renewed, and the ~~the~~ engine and all other hatches efficiently repaired, and the vessel generally put into good and efficient condition.

R. J. Reed.

C. H. Cooke