

Report of Survey for Repairs of Engines and Boilers.

No.

No. in Reg. Book. Survey held at

London

Date, first Survey June 29th Last Survey

1878

10

on the

S.S. "Wagmar"

Master

Tons

425

435

Owners

J. Wyson

Port belonging to

Hull

Classed

Years assigned.

Character in Register Book.

AC1

Diameter of Cylinder

20 1/40

Length of Stroke

26

Pressure of Steam

40 lb

Registered Horse Power

45

Engines made at

Hull

When made

YEAR.

1875

By whom made

Fowler & M'Collin

Particulars of Repairs and Examination

Donkey Boiler found in good condition. Main Boiler found not to require any repairs but to require cleaning this has been done. Crank shaft examined and longitudinal flaws found in two centre bearings but not of a serious nature. Stern shaft found corroded and new end welded on and new lines fitted at after end. All sea cocks ground in. Bilge pipe traced, found that water could be run into ship through the Bilge injection recommended a screw down non return valve to be fitted instead of the cock.

This non return valve has now been fitted

[Signature] 18.7.78

The Amount of Fee ... £ 3 : 3 : 0 received by me

Certificate (if required) ... £

3 Aug 1878

(Travelling Expenses, if any, £)

Committee's Minute

26th July

1878.

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



© 2019

Lloyd's Register Foundation
120N479-0176

Submitted that this record is
eligible to remain as closed

MP

18-7-79



© 2019

Lloyd's Register
Foundation