

# Report of Survey for Repairs of Engines and Boilers.

No. 21584  
 No. in Reg. Book. 414 Survey held at London Date, first Survey Aug 10<sup>th</sup> Last Survey Sept 18<sup>th</sup> 18 78  
 on the S. S. Cleury Master

Built at 1370 Tons 2085 Owners Alford & Co Port belonging to Glasgow When built 1871 Years assigned 8 Character in Register Book 100A1

Diameter of Cylinder 40" x 70" Engines made at Glasgow When made 1871  
 Length of Stroke 42" Pressure of Steam 60lb By whom made London & Glasgow Co  
 Registered Horse Power 250

Particulars of Repairs and Examination Boilers thoroughly scaled & cleaned, a few tubes taken out for this purpose renewed, boilers recaulked &c where necessary, tested to 90lb per square inch satisfactorily. Engines overhauled generally. Thrust Shaft taken out and turned up & new rings fitted to Thrust Block.  
In my opinion, as far as the machinery is concerned this vessel is eligible to remain as classed.

The Amount of Fee ... 9/10 £ 2 : 2 : 0 received by me, James Milton  
 Certificate (if required) ... £ : : 12/6 1878  
 (Travelling Expenses, if any, £ )  
 Committee's Minute 18



Submitted that this vessel is eligible  
to remain as chartered.

MD 19.9.78



© 2019

Lloyd's Register  
Foundation