

Report of Survey for Repairs of Engines and Boilers.

No.

No. in
Reg. Book.

Survey held at London

Date, first Survey

Nov 11

Last Survey

Nov 22

1878

638

on the

S.S. Shoreham

Master

Built at

Port Glasgow

When built

1872

Tons

293
1491

Owners

L. Clarke & Co

Port belonging to

London

Classed

Years
assigned.

Character in Register Book.

90A1

Diameter of Cylinder

24 1/2

Length of Stroke

30

Engines made at

Glasgow

When made

1872

Pressure of Steam

65 lb.

By whom made

Walker Henderson & Co

Registered Horse Power

80

Particulars of Repairs and Examination.

Vessel placed on pontoons & sea connections overhauled & ground in. Propeller taken off and propeller shaft found dangerously flawed. A new shaft fitted and propeller replaced. Engines generally overhauled.

Main Boiler repaired by cutting out bottom portion of combustion chamber back plates and replacing same with new plate and new screw stays. patches fitted to furnaces, and soft patches fitted on bottom both at back and front where leaky.

The boiler & machinery is now in fair condition and in my opinion render the vessel eligible to remain as classed.

The Amount of Fee ...

28/11/78

£

2 : 2 : 0

received by me,

Certificate (if required) ...

£

:

:

28/11/78

Travelling Expenses, if any, £

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

29th November

1878

*Copy of this report
to Mr. H. C. 20/11/78*

Lloyd's Register
Foundation