

\*22463

# Report of Survey for Repairs of Engines and Boilers.

No. 80. (229/11/78)  
No. in Reg. Book. Survey held at Grimby Date, first Survey 10<sup>th</sup> November Last Survey 14<sup>th</sup> December 1878.

27<sup>th</sup> Dec on the Iron screw Steamer "Amsterdam" Master R. Bruce

Tons 587 Owners Rankine & Son Port belonging to Glasgow Classified 100 A1  
323 9.78.

Diameter of Cylinders 2: 22" x 40" Engines made at Dumbarton When made 1878.  
Length of Stroke 42"  
Pressure of Steam 70 lb per sq. inch. By whom made M. Paul & Co.  
Registered Horse Power 115

## Particulars of Repairs and Examination

*On account of damage now done:*  
New intermediate shaft 8 1/4" dia fitted, also new stuffingbox and studs of stern tube, new plumberblock to new shaft new cover of bearing. Eight holding down bolts 1 1/8" dia for bearings in tunnel, one coupling bolt 2 1/8" - 2 3/8" tapered dia. Thrust shaft straightened in the lathe and the remaining shaft in tunnel in the same way examined. Crankshaft examined, also Cylinders and sea connections. New guideblock of july pump fitted and new propeller. In my opinion can remain as classed.

(Condition of Engines and Boilers, and subsequent Repairs and Examinations, to be clearly stated.)

(The Surveyors are requested not to write on or below the space for Committee's Minute).

Damage £2 2 -  
The Amount of Fee ... £ - : - : received by me, 30<sup>th</sup> Dec 1878  
Certificate (if required) ... £ - : - :  
(Travelling Expenses, if any, £ 2. 2. 0)

M. Keywell  
Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute 18



It is submitted that this  
vessel should remain as  
classified M 1071/79



© 2019

Lloyd's Register  
Foundation